

REMONUMENTATION

DEC 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 245

For corners in

INGHAM
(County)
AURELIUS TOWNSHIP
1. Public Land Survey

Located In:	Corner Code #
T <u>2N</u> R <u>2W</u>	<u>B-11</u>
T ___ R ___	___
T ___ R ___	___
T ___ R ___	___
S ___ T ___ R ___	___
S ___ T ___ R ___	___
S ___ T ___ R ___	___
S ___ T ___ R ___	___

2. Property Controlling in Section
3. Miscellaneous Property in Sec.

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

FILED

970041262
10/20/1997 16:12:48
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

I, DAVID L. CLIFFORD, in a field survey on APRIL 14, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5											
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11	31	32	33	34	35	36							
12													
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. ORIGINAL POST SET BY HERVEY PARKE D.S. FEB. 1826.
B.O. 28" S41W 43(28.4)
W.O. 20" N55E 27(17.8)
2. A. JACKSON CO. SURVEYOR USED CORNER IN SURVEY REC. VOL 1. PG 40 MARCH 1839 WITH SAME MONUMENT AND WITNESSES AS GLO.
3. A. JACKSON USED CORNER IN SURVEY IN VOL. 2 PG. 112 IN FEB. 1845 WITH SAME MONUMENT AND WITNESSES AS GLO.
4. T.J. BROWN USED CORNER IN SURVEY REC. VOL. 2 PG. 281 IN JAN. 1866 WITH SAME MONUMENT AND WITNESSES AS GLO.
5. LAVERNE HENDRYX LS 3276 FOUND 1" GAS PIPE AND SET 1/2" REROD ABOVE ACT 74 L2 PG. 401, IN MARCH 1973.
CENTERLINE 10" R. OAK NORTHWEST 45.9'
CENTERLINE 18" DOUBLE W.O. W NW 64.6'
CENTERLINE 18" ASH NORTH 68.1'
6. KAY DON FLUKE LS 18988 RECORDED CORNER IN L6 PG. 295 IN AUG 1986 AS A FOUND #4 BAR.
N20°E 103.65' POWER POLE
N65°E 70.14' WALNUT 17"
SOUTH 11.4' SOUTH EDGE OF ROAD
NORTH 8.8' NORTH EDGE OF ROAD

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" BAR AND CAP IN MONUMENT BOX 2' NORTH OF CENTERLINE BARNES RD. ON OCCUPATION LINE 660' NORTH. PULLED IRON AND EXCAVATED THROUGH BOTTOM OF MONUMENT BOX THROUGH 2ND BIT SURFACE AND FOUND 1" GAS PIPE 18" DEEP BENEATH 1/2" BAR. ACCEPTED PIPE AS PERPETUATION OF CORNER. RETURNED ON APRIL 14, 1997 AND EXCAVATED BOTTOM OF BOX AND FOUND GRANITE STONE ON EAST SIDE OF 1" PIPE. ACCEPTED STONE AND PIPE AS PERPETUATION OF CORNER AND SET 3/4" BAR AND CAP PA 345 LS 25837 ON TOP OF PIPE. MEASURED WEST 2748.85' TO A-11. MEASURED EAST 2652.48' TO C-11. MEASURED SOUTH 2640.57' TO B-12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-11 T2N R2W
3/4" X 24" BAR AND PA 345 CAP LS 25837 IN MONUMENT BOX 2' NORTH OF CENTERLINE BARNES RD.
SET NAIL AND TAG # 28409 IN SOUTHEAST SIDE 22" WALNUT, 61° NAZ., 70.79'
SET NAIL AND TAG # 28409 IN SOUTH SIDE OF 18" WALNUT, 84° NAZ., 275.79'
SET NAIL AND TAG # 28409 IN NORTH SIDE OF 23" CATALPA, 96° NAZ., 256.51'
NORTHWEST CORNER CONCRETE BLOCK FOUNDATION HOUSE # 6221, 106° NAZ., 259.57'
NORTHEAST CORNER CONCRETE BLOCK FOUNDATION BARN, 234° NAZ., 247.74'

Signed by David L. Clifford
Surveyor's Michigan License No. 25837

Date JUNE 2, 1997



P.A. 345 INGHAM COUNTY
PEER APPROVED: 6/2/97 M