

DEC 12 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber

9 Page

246

For corners in

<u>INGHAM</u>	Located in:	Corner Code #
(County)		
AURELIUS TOWNSHIP		
1. Public Land Survey	T <u>2N</u> R <u>2W</u>	<u>B-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

970041263  
10/20/1997 16:12:52  
REGISTER OF DEEDS  
Paula Johnson  
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID L. CLIFFORD, in a field survey on OCT. 24, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

1. POST NOT SET IN ORIGINAL SURVEY
2. T.J. BROWN USED CORNER IN SURVEY REC. VOL.3 PG. 27 IN JAN. 1866 WITH NO MENTION OF MONUMENT OR WITNESSES.



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND EAST-WEST STONE AND TREE ROW WITH NO EVIDENCE OF LOCATION OF CORNER. AFTER TRAVERSE OF SECTION 31 SET STANDARD MONUMENT AT INTERSECTION 1/4 LINES. CORNER FALLS IN EAST-WEST STONE ROW. MEASURED EAST 2651.70' TO C-12. MEASURED WEST 2738.86' TO A-12. MEASURED SOUTH 2641.83' TO B-13. MEASURED NORTH 2639.57' TO B-11

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

B-12 T2N R2W  
3/4" X 24" STEEL BAR AND YELLOW PLASTIC CAP IMPRINTED PA 345 LS 25837 IN MONUMENT IN EAST-WEST STONE ROW.  
NAIL AND TAG IN NORTH SIDE OF 10" SASSAFRAS, 76° NAZ., 8.89'  
NAIL AND TAG IN SOUTH SIDE OF 15" ELM, 91° NAZ., 39.59'  
NAIL AND TAG IN SOUTH SIDE TWIN 18" ELM, 95° NAZ., 59.45'  
LARGE HOLE IN ROCK, 182° NAZ., 9.98'  
NAIL AND TAG # 28409 IN SOUTH SIDE OF 13" SASSAFRAS, 282° NAZ., 5.00'

Signed by David L. Clifford  
Surveyor's Michigan License No. 25837

Date MAY 12, 1997