

Part A continued

5. A LCRC in Liber 2, Page 95 was recorded by Ron Helsel PS #18994 on October 10, 1972, as a found hex head bolt 6" below Bit. Pavem in centerline of Gale Road with the following witnesses:
 S15°E 18" Walnut Nail and Tag 83.72'
 NNW Centerline 30" Maple 104.5'
 N81°E 15" Box Elder Nail and Tag 32.68'
 N73°W Twin 5" Box Elder Nail and Tag 34.93'
6. An Act 132 survey in Liber 1, Page 442 was recorded by Ron Helsel PS #18994 on October 10, 1972. Corner material and witnesses sa as A-5 above.
7. An Act 132 survey in Liber 5, Page 22 was recorded by Kay Don Fluke, PS #18988 on August 8, 1986. Corner refers to Liber 2, Page (same as A-5 above).
8. An Act 132 survey in Liber 6, Page 822 was recorded by Marv Fouty, PS #18989 on October 11, 1991. Corner refers to Liber 2, Page (same as A-5 above).
9. An Act 132 survey in Liber 7, Page 500 was recorded by Ronnie Lester, PS #18998 on February 8, 1995. Corner is noted as a 1 1 hexagon shaped bar, witnessed by:
 Set galvanized nail and 1 1/4" brass tag stamped #18998 LESTER" East side 36" Maple mag. az 348° 103.00'
 Set galvanized nail and 1 1/4" brass tag stamped #18998 LESTER" South side Utility Pole mag. az 97° 59.21'
 Set galvanized nail and 1 1/4" brass tag stamped #18998 LESTER" West side 24" Walnut mag. Az 173° 133.19'
 Northwest Corner of stone foundation mag az 156° 192.48'
10. Ingham County Road Commission grid map calls for corner to be stone and bolt, witnessed by:
 15" Maple NNE 80.3'
 15" Maple NNW 104.5'
 8" Walnut SSE 83.6'

INVESTIGATION
 HERE TO BE
 RECORDED DEEDS
 11/15/1995 13:20:05
 J800000000
 RECORDED

FILED

11/15/95

3 6906

88