

REMONUMENTATION

DEC 1 8 1997

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 247

For corners in COMMISSION

FILED

970041264
10/20/1997 16:12:53
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

INGHAM	Located In:	Corner Code #
(County)		
AURELIUS TOWNSHIP		
1. Public Land Survey	T 2N R 2W	C-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous	S T R	
Property in Sec.	S T R	

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, RONALD L. ENGER, in a field survey on SEPT. 24, 1996 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	6	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11		31										
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

- ORIGINAL POST SET BY HERVEY PARKE D.S. FEB. 1826.
W.O. 34" N67W 5(3.3')
W.O. 34" N77E 38(25.1')
- A. JACKSON CO. SURVEYOR USED CORNER IN MARCH 1839 WITH NEW WITNESSES.
CHERRY 18" S61-3/4W 54-1/3(35.9')
BEECH 20" S50-2/3E 140(92.4')
- T.J. BROWN CO. SURVEYOR USED CORNER IN JAN 1866 WITH SAME WITNESSES AS A-2.
- R. HELSEL LS 18989 FOUND 1" SQUARE STEEL BAR L4 PG 83 ACT 74 AUG. 77.
N45E 134.4' SOUTHWEST CORNER TOP OF SLAB CONCRETE PORCH.
N55E 39.63' NAIL AND TAG IN 24" OAK
S30E 52.47' NAIL AND TAG IN 18" WILD CHERRY
N80W 86.74' NAIL AND TAG IN 36" MAPLE



B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 1/2" BAR AND CAP IN MONUMENT BOX 4.5' NORTH OF CENTERLINE BARNES RD. AND ON CENTERLINE GALE RD.. REMOVED IRON AND EXCAVATED THROUGH BOTTOM OF MONUMENT BOX AND FOUND 1" SQUARE BAR AS CALLED FOR BY R. HELSEL. THIS IS THE TYPE OF BAR FREQUENTLY USED BY ROAD COMMISSION IN 40s AND 50s. PULLED 92.4' S55°E TO REMAINS OF LARGE BEECH STUMP. ACCEPTED 1" BAR AS PERPETUATION OF CORNER BECAUSE OF AGREEMENT WITH HISTORICAL WITNESS AND SET STANDARD BAR AND CAP ABOVE IT. AFTER FURTHER CONSIDERATION RETURNED ON APRIL 14, 1997 AND DUG BOX OUT AND FOUND GRANITE STONE ON EAST SIDE 1" SQUARE BAR. ACCEPTED 1" SQUARE BAR AS PERPETUATION OF CORNER AND RESET 3/4" BAR 345 RLS 25837 CAP. MEASURED WEST 2652.48' TO B-11, MEASURED SOUTH 2658.51 TO C-12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

C-11 T2N R2W
3/4" X 24" BAR AND PA345 CAP PS 28409 IN MONUMENT BOX ON CENTERLINE GALE RD AND 4.5' N OF CENTERLINE BARNES RD. SOUTHWEST CORNER CONCRETE PORCH, 46° NAZ., 134.40'
FOUND NAIL AND TAG # 28414 IN SOUTH SIDE OF 30" OAK, 59° NAZ., 39.00'
SET NAIL AND TAG # 28409 IN SOUTH SIDE OF 19" MAPLE, 82° NAZ., 102.75'
SET NAIL AND TAG # 28409 IN NORTH SIDE OF 10" WALNUT, 105° NAZ., 144.95'
SET NAIL AND TAG # 28409 IN SOUTH SIDE OF 5" TWIN MAPLE, 284° NAZ., 118.40'

Signed by David L. Clifford
Surveyor's Michigan License No. 25837

Date JUNE 2, 1997

P.A. 345 INGHAM COUNTY
PEER APPROVED 6/2/97 *MC*