

G-1, T2N, R2W

Part A - Continued

- 4). 01-01-1969: County Road Commission Corner Grid Sheet calls for a stone and brick; 15" Elm NW 41.8 feet, anchor post SW 40.5 feet, anchor post NE 57.4 feet.
- 5). 02-13-1973: Land Corner Recordation Certificate (Rec. 2-15-73, L2-P349), L. J. Hendryx, L.P.S. 3276 states "in 1945 a pointed stone was witnessed: NE cor. House SW 114.45 feet, center of 18" Oak NW 69.2 feet, SW cor. Store NE 72.65 feet, set #4 iron at surface from old witnesses; NE cor. House SW 114.45 feet, center of 18" Oak NW 69.2 feet, SW cor. House NE 72.65 feet."
- 6). 02-13-1973: Certified Survey Map (Rec. 2-15-73, L1-P630), L. J. Hendryx notes the NW Corner, Sec. 3, T2N, R2W and calls for a "pointed stone, #4 iron at surface."
- 7). 04-02-1973: Land Corner Recordation Certificate for G-13, T3N, R2W (Rec. 5-11-73, L2-P413), R. M. Lester, L.P.S. 18998 "set 1/2" bar (G-13) on townline recorded falling from found NW Corner Sec. 3, T2N, R2W (G-1)."
- 8). 04-04-1973: Certified Survey Map (Rec. 5-11-73, L1-P718), R. M. Lester notes "NW Cor. Sec. 3, T2N, R2W, found 1/2" bar" 19.8 feet West of G-13, T3N, R2W.
- 9). 08-31-1994: Certified Survey Map (Rec. 11-15-94, L7-P386), Ron Helsel, L.P.S. 18994 "found plow point surrounded by rocks, red brick, and sandstone at a depth of 1 foot, approximately 1.4 feet south from the C/L Nichols Road and 7.4 feet west from the C/L Eifert Road (set collar with lid over plow point). Found axle shaft surrounded by rocks, red brick, and sandstone at G-13, T3N, R2W East 19.70 feet, found nail and tag (no ID.) in S. side 24" Oak N60°W 68.36 feet, found nail and tag 25832 (L. A. Bryan) in E. side 18" Cherry S10°W 126.10 feet, NE corner of House S40°W 114.31 feet, SW corner of House #506 N55°E 67.35 feet." He also gives a distance of 2656.90 feet to H-1.

RECORDED
INDEXED
1994
104