

SURVEY &  
REMONUMENTATION

DEC 16 1996

LAND CORNER RECORDATION CERTIFICATE Liber 9 Page 107  
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION  
For corners in

<u>INGHAM COUNTY</u> Aurelius Township	Located In:	Corner Code #
1. Public Land Survey	T <u>2N</u> R <u>2W</u>	<u>G-3</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

FILED

960045754  
12/02/1996 09:31:43  
REGISTER OF DEEDS  
Paula Johnson  
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Richard W. Steadman, in a field survey on August 21, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3							●						
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: U. S. Public Land Survey Field Notes, Deputy Surveyor Harvey Parke "set post, corner to Secs. 3, 4, 9, and 10 from which bears 6" Lynn N31-1/2°W 15 links and 12" Beech S56°E 18-1/2 links."
- 12-11-1845: Record of Surveys, Vol. 1, Pages 181 and 182, County Surveyor Anson Jackson used this corner and notes the U. S. witnesses.
- 01-13-1866: Record of Surveys, Vol. 3, Page 21, Deputy County Surveyor T. J. Brown used this corner but gives no information about it other than referring to it as "the SW corner of the section (no bearing trees)."

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron pipe and cap 11370 in good condition in monument box. Measured 2643.42 feet to G-2 and 2654.52 feet to H-3.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Left the 3/4" iron pipe and cap 11370 over stone in monument box to mark the corner and took the following witnesses (bearings are magnetic):

- Found nail and tag 11370 in W. side Power Pole N49°E 58.50 feet
- Found nail and tag 11370 in E. side cut off Telephone Pole S15°E 70.96 feet
- Set nail and tag 11370 in E. side 40" Box Elder N13°W 131.63 feet
- Set nail and tag 11370 in S. side Power Pole N68°W 114.22 feet
- Set nail and tag 11370 in S. side Power Pole S83°W 138.42 feet



Signed by Richard W. Steadman

Date November 4, 1996

Surveyor's Michigan License No. 11370

G-3, T2N, R2W

Part A - Continued

- 4). 05-01-1895: Record of Surveys, Vol. 3, Page 232, County Surveyor W. A. Rowe calls for a stone, brick, and crockery witnessed by a 12" Sugar N60°W 144 links and a 6" Sugar S71-1/4°E 150 links (99 feet).
- 5). 01-10-1969: County Road Commission Corner Grid Sheet calls for a stone and brick witnessed by 8" Maple WNW 76.0 feet, 14" Maple ENE 99.7 feet, anchor post NE 37.0 feet.
- 6). 07-05-1973: Land Corner Recordation Certificate (Rec. 7-29-75, L3-P418), R. W. Steadman, L.P.S. 11370 "dug hole in the intersection of Columbia and Eifert Roads and found a 1/2" iron pipe alongside a pointed stone with broken brick around it. All the Road Commission witnesses are gone. Removed the 1/2" pipe and raised the location of the stone to the surface with a 3/4" iron pipe in a monument box; Power Pole NE 58.44 feet, 18" Walnut SE 82.58 feet, Telephone Pole SSE 71.00 feet."
- 7). 01-06-1976: Certified Survey Map (Rec. 9-16-77, L2-P1271), L. J. Hendryx, L.P.S. 3276 notes "SE Corner of Section 4, T2N, R2W."
- 8). March 1980: Certified Survey Map (Rec. 3-24-80, L3-P1229), A. C. Williams, L.P.S. 21275 calls for the SE Cor. Sec. 4, T2N, R2W and gives the same witnesses as Item 6 above. He also gives distances of 2645.24 feet to G-2 and 2668.80 feet to F-3.
- 9). March 1980: Certified Survey Map (Rec. 3-24-80, L3-P1233), A. C. Williams again calls for the SE Cor. Sec. 4, T2N, R2W and gives the same witnesses as Item 6 above and the same distances as Item 8 above.
- 10). 10-28-1982: Certified Survey Map (Rec. 10-19-83, L4-P760), R. W. Steadman calls for the same mounument and witnesses given in Item 6 above. He also gives a distance of 2654.40 feet to H-3.