

SURVEY & REMONUMENTATION

DEC 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 102

For corners in

INGHAM COUNTY Located In: _____ Corner Code # _____
Aurelius Township

- | | | |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey | T <u>2N</u> R <u>2W</u> | <u>H-2</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILED
960045751
12/02/1996 09:31:37
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Richard W. Steadman, in a field survey on September 20, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 01-12-1844: The section Center was not set by the U. S. Survey of the Public Lands. It appears to have been established by County Surveyor Anson Jackson in a survey recorded in Record of Surveys, Vol. 1, Page 99; witnesses: 6" Tamarack S11-3/4°W 12 links and 6" Tamarack N73-1/2°E 6 links.
- 01-13-1866: Record of Surveys, Vol. 3, Page 21, Deputy County Surveyor T. J. Brown used this corner, calling for "post in the center of the section" and notes the witnesses from Item 1 above.
- I find no other references to this corner in public records.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched the suspected location of corner but found only fence wire on the ground running North-South and broad field lines East-West. Re-established corner at intersection of the quarterlines by traverse. Location falls in down north-south fence wire, and appears to fit field lines east and west. Measured 2644.77 feet to H-3, 2679.49 feet to H-1, 2655.96 feet to G-2, and 2661.16 feet to I-2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set standard Ingham County Remonumentation 3/4" smooth iron rod and cap stamped "P. A. 345 PS 11370" to mark the corner and took the following witnesses (bearings are magnetic):

Set nail and tag 11370 in W. side 12" Cherry N02°E 52.85 feet
Set nail and tag 11370 in N. side 8" Elm S89°E 21.97 feet
Set nail and tag 11370 in NE side 8" Willow S20°E 20.82 feet
Set 5/8" Iron Rod N55°W 25.17 feet (Traverse Point AU2-19-13)



Signed by Richard W. Steadman Date November 9, 1996

Surveyor's Michigan License No. 11370