

REMONUMENTATION

DEC 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber

9 Page 111

For corners in

<u>INGHAM COUNTY</u>	Located In:	Corner Code #
Aurelius Township		
1. Public Land Survey	T <u>2N</u> R <u>2W</u>	<u>H-3</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

FILED
960045756
12/02/1996 09:31:46
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3							●					
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, Richard W. Steadman, in a field survey on August 21, 1996, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1826: U. S. Public Land Survey Field Notes, Deputy Surveyor Harvey Parke at 40.16 chains "set 1/4 post at average distance and on true line, from which bears 10" Beech N53°E 15-1/2 links and 14" Beech S15-1/2°W 26 links."
- 12-11-1845: Record of Surveys, Vol. 1, Page 182, County Surveyor Anson Jackson used this corner and notes the U. S. witnesses.
- 01-13-1866: Record of Surveys, Vol. 3, Page 21, Deputy County Surveyor T. J. Brown used this corner, but gives no information about it other than referring to it as "the quarter post on the south line of the section (no bearing trees)."

(Continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Opposite fence and tree line South and about 2 feet south of C/L Columbia Road, found 3/4" iron pipe and cap 11370 in good condition in monument box. Measured 2654.52 feet to G-3, 2664.78 feet to I-3, and 2644.77 feet to H-2.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Left the 3/4" iron pipe and cap 11370 in monument box to mark the corner and took the following witnesses (bearings are magnetic):

- Found nail and shiner in E. side Fence Post S06°W 27.30 feet
- Set nail and tag 11370 in N. side 10" Cedar S84°W 128.90 feet
- Found nail and tag 11370 in N. side Power Pole N67°W 145.62 feet
- SW corner House Foundation N11°E 229.25 feet
- Found nail and tag 11370 in S. side Power Pole N80°E 159.71 feet



Signed by Richard W. Steadman
Surveyor's Michigan License No. 11370

Date November 9, 1996

