

I-1 T2N R2W
PART A CONTINUED

2. T.J. BROWN, COUNTY SURVEYOR, REPORTED USING CORNER IN A SURVEY DATED JAN. 11, 1866, AND RECORDED VOL. 1, PAGE 21, COUNTY SURVEYORS RECORDS AS A STONE WITH NO WITNESSES.
3. MARGINAL NOTE ON A DUPLICATE OF SURVEY IN ITEM 2:
APRIL 14, 1925
FOUND OLD STAKE AND SET IRON AT NW CORNER SEC. 2 - 23 1/2' EAST TO ANC. POST
RAN LINE 1/2 MILE EAST FOR NEW FENCE A.N. BATEMAN
4. INGHAM COUNTY ROAD COMMISSION INFORMATION FROM 1964 CALLS FOR A 1" BOLT WITH THESE WITNESSES:
P.P. N.N.W. 115.58'
3/4" IRON E. 70.04'
P.P. W.S.W. 55.62'
DISTANCE I-1 TO I-2 - 2662.84
5. RONNIE M. LESTER LS #18998 RECORDED CORNER ON APRIL 28, 1978, IN LIBER 4 OF CORNERS, PAGE 194, INGHAM COUNTY RECORDS AS A FOUND BOAT SPIKE SUBSEQUENTLY REPLACED BY A 1" RECTANGULAR BAR IN MONUMENT BOX WITH THE FOLLOWING WITNESSES:
NAIL AND TAG IN NORTH SIDE FENCE CORNER POST, EAST 11.67'
NAIL AND TAG IN SE SIDE 15" PINE, ESE 127.30'
NAIL AND TAG IN WEST SIDE 15" PINE, SE 172.18'
6. GEORGE YOUNG LS #17640 USED CORNER IN A SURVEY ON APRIL 11, 1979, RECORDED IN LIBER 3 OF SURVEYS, PAGE 845, AND USED AGAIN IN A SURVEY ON NO. 15, 1983, RECORDED IN LIBER 4 OF SURVEYS, PAGE 777, AS A 1" BAR IN MONUMENT BOX WITH SAME WITNESSES AS IN ITEM #5