

1993

COMMISSION

P11-72-253-J8
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 7 PAGE 334

FILED

For corners in

<u>Ingham</u> (County)	Located In:	Corner Code #:
1. Public Land Survey	T <u>2N</u> R <u>2W</u>	<u>J-8</u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
	T <u> </u> R <u> </u>	<u> </u>
2. Property Controlling in Section	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
3. Miscellaneous Property in Sec.	S <u> </u> T <u> </u> R <u> </u>	<u> </u>
	S <u> </u> T <u> </u> R <u> </u>	<u> </u>

AUG 12 12 38 PM '93

REGISTER OF DEEDS
[Signature]
INGHAM COUNTY, MICH.

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	5	4	3	2	1							
3												
4	7	6	5	4	3	2	1					
5												
6	10	9	8	7	6	5	4	3	2	1		
7												
8	13	12	11	10	9	8	7	6	5	4	3	2
9												
10	16	15	14	13	12	11	10	9	8	7	6	5
11												
12	19	18	17	16	15	14	13	12	11	10	9	8
13												

I, Ronnie M. Lester, in a field survey on June 07, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

J-8, Center of Section 23, No record of this corner being established in original government survey. A. Jackson, County Surveyor, established corner in survey dated 03/16/1848. No specific monument noted. Witnesses: W ash, 16" N17°W, 33 links and sugar, 8" S54 1/2°E, 9 links. Volume 2, Page 54. A. Jackson, County Surveyor noted corner again in survey recorded Volume 2, Page 214 dated 10/19/1854. No specific monument noted. Witnesses same as previous survey. T.J. Brown utilized corner in survey recorded 06/05/1876 in Volume 3, Page 122 of County Surveyors notes. Brown called for "post" with one witness of 16" w. ash bearing N 17° W 33 links distant. No recent or modern data on this corner other than Remonumentation crew excavated at this site on 12/20/1978 under supervision of L. Bryan. No data other than old fence corner post found at that time.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-8 Investigation at this corner location by this surveyor revealed old fence corner post with remains of fences North, South, East, and West. Accepted old fence corner post as perpetuated location of Center of Section as established by Jackson and perpetuated by other surveys. Measured East 2652.70' (Co. Surv. record 2643.30) Measured West 2653.03' (Co. Surv. record 2640) Measured South 2650.28 (Co. surv. record 2647.92) Measured North 2649.60'. Found corner to be 0.32' North of East-West 1/4 line and 0.10 East of North-South 1/4 line. Set 3/4" x 24" pointed bar at base of fence post and set 1/2" bar and cap adjacent.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-8 Center of Section 23, T2N, R2W, Aurelius Township.
3/4" x 24" bar as noted above with 1/2" bar and cap adjacent.
witnesses:

- Set nail and brass tag in South side 36" multi basswood, 58° az., 9.85'
- Set nail and brass tag in East side 10" hickory, 322° az., 8.05'
- Set nail and brass tag in East side 12" hickory, 353° az., 3.35'
- Set nail and brass tag in West side twin 10" ash, 172° az., 25.45'



Signed by Ronnie M. Lester Date June 15, 1993
Surveyor's Michigan License No. 18998

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS, JAN. 26, 1971
REVISED MAY 14, 1975
REVISED JAN., 1983
P.A. 345 INGHAM COUNTY
PEER APPROVED 4 AUGUST 1993

2480

filed 9/17/93