

DEC 17 1998

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 332

SECTION

For corners in

<u>INGHAM</u> (County)	Located In:	Corner Code #
	WHEATFIELD	TOWNSHIP
1. Public Land Survey	T <u>3N</u> R <u>1E</u>	<u>A-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

940047783
09/18/1998 13:20:27
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

I, RON HELSEL, in a field survey on JULY 8, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL MONUMENT: POST SET BY U.S. DEPUTY SURVEYOR, JOSEPH WAMPLER, MAR., 1826. WITNESSED AS: SUGAR 6", S66E, 6 1/2 LINKS; LYNN 33", N59E, 46 LINKS.

1) LIBER 4, PAGE 99 OF CORNERS, DATED JUNE 9, 1977, G. YOUNG P.S. NO. 17640, "SET CORNER ON SECTION LINE AT A PRORATED DISTANCED MEASURED BETWEEN SW CORNER SECTION 19 & NW CORNER SECTION 18, T3N, R1E. SET 1/2" REROD WITH CAP."

#16 NAIL & CAP IN 18" ASH, N20E, 148.65' (GONE)

#16 NAIL & CAP IN 18" ASH, N40E, 52.12' (FOUND)

#16 NAIL & CAP IN 15" ASH, N80E, 107.25' (FOUND)

2) P.A. 345 SURVEY, LIBER 3, PAGE 19, DATED 6-18-1977 BY G. YOUNG CALLED FOR THE SAME WITNESSES AND CORNER AS ABOVE.

3) P.A. 345 SURVEY, LIBER 7, PAGES 233-235, DATED 5-13-1993 BY D. LOHR #30090, "FD. 1/2" IRON, 2' DEEP, 2 FT. WEST C/L MERIDIAN ROAD AND 4' NORTH C/L HOLT ROAD."

RESET N&T 30090 24" ASH, N77E, 107.25' (FOUND)

SET N&T 30090 8" PINE, S64E, 82.24' (FOUND)

RESET N&T 30090 24" ASH, N14E, 148.65' (GONE)

SET N&T 30090 12" TREE N19E, 108.90' (FOUND MAPLE TREE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" REBAR 2 FEET WEST OF C/L MERIDIAN ROAD AND 3.5 FEET NORTH OF THE C/L OF HOLT ROAD TO THE EAST. TRAVERSE DETERMINED THE BAR TO BE ON THE STANDARD LINE BETWEEN M-7 AND M-6 OF ALAIEDON TWP., T3N, R1W OF THE PRINCIPLE MERIDIAN. EXCAVATED DOWN THROUGH 3 LAYERS OF ASPHALT ABOUT 3 FEET TO THE CLAY ROAD BED. DID NOT FIND ANY EVIDENCE OF A PREVIOUS CORNER. ACCEPTED THE POSITION OF THE BAR AS FAITHFUL PERPETUATION OF THE CORNER AND REPLACED IT WITH A 3/4" X 24" FORM PIN AND DISK STAMPED P.A. 345, P.S. 18994 IN A MONUMENT BOX AT THE SURFACE OF MERIDIAN ROAD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" IRON FORM PIN AND AN INGHAM COUNTY DISK IN A MONUMENT BOX 2 FEET WEST C/L OF MERIDIAN ROAD.

FOUND NAIL & TAG # 30090, N/SIDE 8" PINE, AZ. 126°, 82.26 FEET

SET NAIL & TAG NO. 18994, W/SIDE 24" ASH, AZ. 52°, 51.50 FEET

SET NAIL & TAG NO. 18994, W/SIDE 14" MAPLE, AZ. 27°, 108.70 FEET

SET NAIL & TAG NO. 18994, S/SIDE 20" ASH, AZ. 83°, 107.19 FEET

FACE OF 6" STEEL POST IN CONC., AZ. 123°, 70.65'

MEASURED SOUTH, 1553.04 FEET TO M-7 OF T3N, R1W

MEASURED NORTH, 2634.79 FEET TO A-6

MEASURED NORTH, 1085.56 FEET TO M-6 OF T3N, R1W



Signed by Ron Helsel

Date Aug. 8, 1998

Surveyor's Michigan License No. 18994