

REMONUMENTATION

DEC 1 2 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 242

For corners in

<u>INGHAM</u> (County)	Located In:	Corner Code #
	WHEATFIELD TOWNSHIP	
1. Public Land Survey	T <u>3N</u> R <u>1E</u>	<u>C-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

970041161  
10/20/1997 13:41:44  
REGISTER OF DEEDS  
Paula Johnson  
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, RON HELSEL, in a field survey on JUNE 13, 1997  
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points  
mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as  
required in the current manual of survey instructions of the United States Department of the Interior,  
Bureau of Land Management or by a decree of a Court of Law and /or that the corner points  
mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of  
Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented,  
re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	I
1												
2	6		5		4		3		2		1	
3												
4	7	●	8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded  
on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
ORIGINAL MONUMENT: POST SET BY J. WAMPLER, U.S. DEPUTY SURVEYOR, MARCH  
3, 1826. LYNN 32" N35W, 10 LINKS; BEECH 8" S66E, 12 LINKS; MARGINAL  
WITNESS: BEECH 28", N40 2/3W, 19 1/2 LINKS, (SOURCE UNKNOWN).

1) FROM THE CETA REMON. DOSSIER: FOLDER 1, PAGE 11, W. H. RAYNER, COUNTY  
SURVEYOR, JUNE 23, 1865 CALLED FOR A BEECH 6", N59 1/2E, 86 LINKS; ELM 8", N78 1/4W, 68 1/2LINKS. NO MONUMENT  
DESCRIBED FOR CORNER.  
2) A L.C.R.C. WAS RECORDED IN LIBER 7, PAGE 312 BY L.BRYAN, P.S. NO. 25832, FIELD DATED DEC. 3, 1992, (SURVEY  
UNRECORDED JOB 92-B-39874). "CORNER ESTABLISHED JUNE 23, 1865 BY W.H. RAYNER, COUNTY SURVEYOR. SET BAR & CAP  
#25832 IN HOLE OF OLD ANCHOR POST ON EAST-WEST FENCE LINE. MEASUREMENTS IN CLOSE ACCORD WITH COUNTY  
SURVEYOR AND G.L.O. RECORDS."  
SET NAIL & TAG #25832 NORTH SIDE 16" OAK, S45E, 12.75'  
SET NAIL & TAG #25832 NORTHWEST SIDE 10" OAK, N50E. 8.12'  
SET NAIL & TAG #25832 SOUTH SIDE 8" ASH, N88W, 8.30'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND THE 1/2" BAR AS DESCRIBED IN 2-A ABOVE, ALONG WITH ALL (3) REMAINING TAGS AND BEARING TREES, IN A HOLE OF  
A ROTTED 12" WOOD ANCHOR POST, ON LINE WITH REMAINS OF FENCE TO THE EAST AND WEST. EXCAVATED AND FOUND  
WHAT APPEARED TO BE AN OLD OXIDIZED PAIL FILLED WITH SMALL STONES ON THE EASTERLY SIDE OF THE POST ABOUT 10"  
FROM THE 1/2" BAR. ACCEPTED THE POSITION OF THE 1/2" BAR AND CAP AS SET BY SURVEYOR BRYAN AND SUPPORTED BY THE  
PAIL OF STONES AS FAITHFUL PERPETUATION OF THE RAYNER CORNER SET IN 1865. LEFT THE BAR AND CAP IN ITS ORIGINAL  
POSITION AND SET NEW WITNESS NAILS AND TAGS ABOVE THE FOUND BRYAN TAGS.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
1/2" BAR AND CAP NO.25832 ON EAST-WEST FENCE LINE 755 FEET MORE OR LESS EAST FROM THE C/L OF MERIDIAN ROAD.

SET NAIL AND TAG NO. 18994 NE/SIDE 18" OAK, AZ. 155 DEG., 12.74 FEET  
SET NAIL AND TAG NO. 18994 NW/SIDE 10" OAK, AZ. 73 DEG., 8.22 FEET  
SET NAIL AND TAG NO. 18994 S/SIDE 8" ASH, AZ., 300 DEG., 8.36 FEET  
SET NAIL AND TAG NO. 18994 N/SIDE 10"ASH, AZ. 230 DEG., 13.80 FEET  
SET NAIL AND TAG NO. 18994 E/SIDE 12" ASH, AZ. 325 DEG., 21.65 FEET



Signed by Ron Helsel Date SEPT 27, 1997  
Surveyor's Michigan License No. 18994

P.A. 345 INGHAM COUNTY  
PEER APPROVED: 9/25/97