

DEC 17 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber

9 Page 333

For corners in

| | | |
|------------------------------------|-------------------------|---------------|
| <u>INGHAM</u> | Located In: | Corner Code # |
| (County) | WHEATFIELD TOWNSHIP | |
| 1. Public Land Survey | T <u>3N</u> R <u>1E</u> | <u>C-6</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

FILED

980047784
09/18/1998 13:20:29
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, RON HELSEL, in a field survey on JULY 1, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | | | | | | | | | | | |
|----|----|---|----|---|----|---|----|---|----|---|----|
| A | B | C | D | E | F | G | H | I | J | K | L |
| 1 | | | | | | | | | | | |
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 |
| 3 | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 |
| 5 | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | | 14 | | 13 |
| 7 | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 |
| 9 | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 |
| 11 | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 |
| 13 | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL MONUMENT: POST SET BY JOSEPH WAMPLER, U.S. DEPUTY SURVEYOR, MAR., 1826. WITNESSED AS: BEECH 18", S70W, 2 LINKS; BEECH, 17", S84E, 19 LINKS
1) A MARGIN NOTE IN THE INGHAM COUNTY COPY OF THE G.L.O. NOTES CALLS FOR A STONE. NO DATE GIVEN AND INITIALED ILLEGIBLY.
2) I DID NOT FIND ANY RECORDS PUBLIC OR PRIVATE THAT CALLS FOR THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND A 3-WAY FENCE TO THE NORTH, SOUTH AND EAST WITH A 2" BY 2" ANGLE IRON ANCHOR POST ENCASED IN A 5 FOOT DIAMETER CONCRETE BASE. FOUND A PLOW POINT AND A 15" X 8" DIAMETER POINTED BLUE STONE LYING ON THE GROUND NEXT TO THE ANCHOR POST, ALONG WITH SEVERAL SMALLER STONES POSITIONED IN A CIRCLE AROUND IT. ALSO FOUND THE ROTTED REMAINS OF AN OLD WOOD ANCHOR POST AND A PIECE OF OXIDIZED PIPE ABOUT 4" LONG. I BELIEVE THAT THE STONE, SECTION OF PIPE, AND PLOW POINT WAS REMOVED WHEN THE ANGLE IRON ANCHOR POST WAS SET. ACCEPTED THE POSITION OF THE NORTHWEST CORNER OF THE STEEL POST AS FAITHFUL PERPETUATION OF AN UNRECORDED COUNTY SURVEYOR MARKER. SET A 3/4" FORM PIN AND DISK STAMPED P.A. 345, P.S. 18994, 2.84 FEET WEST OF THE ANCHOR POST TO CONFORM WITH P.A. 74.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
NORTHWEST CORNER OF A 2" x 2" STEEL ANCHOR POST AT INTERSECTION OF FENCES TO EAST, NORTH, AND SOUTH
3/4" BY 24" FORM PIN AND ALUMINUM DISK, WEST, 2.84 FEET
SET NAIL & TAG #18994 ON N/SIDE OF 10" MAPLE, AZ. 87°, 57.5 FEET
SET NAIL & TAG #18994 ON N/SIDE OF TWIN 18" OAK, AZ. 95°, 9.35 FEET
SET NAIL & TAG #18994 ON E/SIDE OF 6" ELM, AZ.04° 6.40 FEET
SET NAIL & TAG #18994 ON E/SIDE OF 4" THORN APPLE, AZ. 339°, 12.95 FEET



Signed by Ron Helsel Date Aug 7, 1998
Surveyor's Michigan License No. 18994