

DEC 17 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 334

For corners in

<u>INGHAM</u> (County)	Located In: WHEATFIELD TOWNSHIP	Corner Code # C-7
1. Public Land Survey	T <u>3N</u> R <u>1E</u>	<u>C-7</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

980047785
09/18/1998 13:20:31
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, RON HELSEL, in a field survey on OCTOBER 1997 & JULY 7, 1998 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL MONUMENT: POST SET BY JOSEPH WAMPLER, U.S. DEPUTY SURVEYOR, MAR., 1826. WITNESSED AS: LYNN, 14", S46E, 7 1/2 LINKS; LYNN, 8", S67 1/2W, 28 LINKS

- 1) INGHAM CO. ROAD GRID MAP CALLS FOR STONE, AND GLASS. 12" OAK, SW.63.3'; 12" OAK, SW, 66.3'; FW ELM SE, 61.9'
- 2) LIBER 2, PAGE 183 OF CORNERS, DATED JULY 28, 1972, F.N. WHITE P.S. NO. 12034. "FOUND 1/4" REINFORCEMENT BAR; 1" BELOW BLACKTOP SURFACE ON FENCE LINES TO NORTH AND SOUTH."

SET NAIL IN NORTH SIDE 18" WALNUT S40E 37.85' (FOUND WALNUT)
 1/2" IRON IN FENCE TO SOUTH SOUTH 33.08' (FOUND 1/2" REBAR)
 SET NAIL IN EAST SIDE 20' WALNUT N45W 43.65' (FOUND WALNUT)

- 3) P.A. 132 SURVEY RECORDED IN LIBER 4, PAGE 267, DATED MAR. 11, 1981 BY G. YOUNG NO. 17640. HE CITED THE SAME WITNESSES AND CORNER AS RECORDED IN THE L.C.R.C. ABOVE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

EXCAVATED THIS CORNER IN OCTOBER OF 1997 AND FOUND A VERY RUSTED BOLT SPIKE OVER A 1/4" REBAR BELOW THE SURFACE OF AND ONE FOOT NORTH OF THE C/L OF HOLT ROAD. EXCAVATED DOWN TO THE CLAY ROAD BED AND FOUND A CIRCLE OF GLASS BELOW THE SPIKE 2.5' DEEP. POSITION WAS ON LINE WITH THE FENCES TO THE NORTH AND SOUTH AS DESCRIBED BY SURVEYOR WHITE. RETURNED TO SITE ON JULY 2, 1998 AND FOUND HOLT ROAD HAD BEEN RESURFACED AND A MONUMENT BOX HAD BEEN SET OVER THE SPIKE AND WAS ENCASED WITH CONCRETE. ACCEPTED THE POSITION OF THE BOLT SPIKE AND CIRCLE OF GLASS AS FOUND IN OCTOBER 1997 AND SET AN ALUMINUM MAGNETIC DISK OVER THE SPIKE AND ADDED A 3" LAYER OF CONCRETE TO HOLD IT IN PLACE ON JULY 7, 1998.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3" ALUMINUM MAGNETIC DISK STAMPED P.A. 345, P.S. NO. 18994 OVER BOLT SPIKE IN MONUMENT BOX.
 SET NAIL & TAG #18994 ON NE/SIDE OF 28" WALNUT, AZ. 140°, 38.48 FEET
 SET NAIL & TAG #18994 ON S/SIDE OF 14" ELM, AZ. 69°, 56.16 FEET
 SET NAIL & TAG #18994 ON NE/SIDE OF 28" WALNUT, AZ. 313°, 43.70 FEET
 SET NAIL & TAG #18994 ON N/SIDE OF 16" WALNUT, AZ. 107°, 135.51 FEET
 CORNER OF ANGLE IRON ANCHOR POST, NORTH, 24.9'
 1/2" REBAR IN FENCE LINE, SOUTH, 33.04 FEET



Signed by Ron Helsel
Surveyor's Michigan License No. 18994

Date Aug. 8, 1998