

JAN 18 2001

Paula Johnson
INGHAM COUNTY
REGISTER OF DEEDS
RON HELSEL

L-9 P-576

RECORDED
CRNR 9.00

2000-043480

SECTION

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

WHEATFIELD TOWNSHIP

For corners in

INGHAM Located In: Corner Code #
(County)

- 1. Public Land Survey T 3N R 1E G-1
T ___ R ___
T ___ R ___
T ___ R ___
- 2. Property Controlling S ___ T ___ R ___
in Section S ___ T ___ R ___
- 3. Miscellaneous S ___ T ___ R ___
Property in Sec. S ___ T ___ R ___



2000-043480
Page: 1 of 1
10/12/2000 08:08A

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, RON HELSEL, in a field survey on JULY 15, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL MONUMENT: POST SET BY J. WAMPLER, US DEPUTY SURVEYOR, 1826.
74.42 CHAINS FROM G-3 INTERSECT BOUNDARY 82 LINKS WEST OF POST.
B. OAK 40", S55W 5 LINKS; BEECH 14", S38E, 46 LINKS.
FOUND NO RECORDS PRIVATE OR PUBLIC CONCERNING THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
MEASURED G.L.O. FALLING OF 82 LINKS WEST OF G-13 WILLIAMSTOWN TWP. T4N, R1E, (54.12 FEET). EXCAVATED ALONG EAST-WEST REMNANTS OF A FENCE LINE DOWN 12" MORE OR LESS AND FOUND WIRE WRAPPED AROUND A PLOW POINT AT A DISTANCE OF 54.3 FEET WEST OF G-12 IN A CIRCLE OF FIELD STONES, ALSO FOUND A 1" BY 1/4" WIDE IRON BAND ABOUT 8" LONG NEXT TO THE PLOW POINT. ACCEPTED THIS POSITION AS FAITHFUL PERPETUATION OF THE CORNER AND REPLACED THE PLOW POINT WITH A STANDARD 3/4" BY 24" FORM PIN AND ALUMINUM DISK STAMPED P.A. 345, P.S. 18994. SET THE PLOW POINT ON THE EAST SIDE OF THE PIN AND DISK AND A POINTED STONE ON THE WEST SIDE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
3/4" IRON PIN AND STANDARD INGHAM COUNTY DISK 82 FEET SOUTH OF THE SOUTHERLY RIGHT OF WAY OF THE C&O RAILROAD.
EAST, 54.30 FEET TO G-13, T4N, R1E WILLIAMSTOWN TOWNSHIP)
SET NAIL AND TAG NO. 18994 SE/SIDE 20" MAPLE, N. AZ. 130°, 2.42 FEET
SET NAIL & TAG NO. 18994 W/SIDE 20" MAPLE, N. AZ. 175°, 24.15 FEET
SET NAIL & TAG NO. 18994 S/SIDE TWIN 22" OAK, N. AZ. 265°, 27.45 FEET
SET NAIL & TAG NO. 18994 E/SIDE 8" BASSWOOD, N. AZ. 11°, 27.21 FEET

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													



Signed by Ron Helsel
Surveyor's Michigan License No. 18994

Date 9-14-00