

DEC 14 1993

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 8 PAGE 41
FILED

For corners in

<u>INGHAM</u> (County)	Located In:	Corner Code ://
1. Public Land Survey	T <u>3N</u> R <u>1E</u>	<u>G-9</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Nov 24 9 03 AM '93

REGISTER OF DEEDS
Ingham County, Mich.

Register of Deeds Stamp & File Number

WHEATFIELD TOWNSHIP

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MAURICE H. MAHIEU, in a field survey on SEPTEMBER 20, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- ORIGINAL CORNER WAS POST SET BY JOSEPH WAMPLER IN DEC. 1826,
WITNESSED BY: LYNN 6" S 67 1/2° E 9 LKS
BEECH 13" S 38° W 24 LKS
- CORNER WAS USED BY W. H. RAYNER COUNTY SURVEYOR ON JAN. 16, 1867 AS NOTED IN FOLDER 1, PAGE 35, COUNTY SURVEY RECORDS. CORNER MONUMENTATION IS NOT NOTED BUT WITNESSED BY:
ASH N 44° E 42 LKS
W. O. 24" S 45° E 101 LKS

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" PIPE IN CENTERLINE OF FROST ROAD (GRAVEL SURFACE) ON LINE WITH FENCE LINE TO SOUTH. SEARCHED FOR IRON (A-4 & A-5) IN AREAS OTHER THAN LOCATION OF FOUND 1/2" PIPE. LOCATION OF FOUND 1/2" PIPE APPEARS TO BE THE PERPETUATED LOCATION OF THE CORNER AND ACCEPTED 1/2" PIPE AS CORNER. ALSO FOUND 2 "POLARIS SURVEYING" WITNESS 15" MAPLE S 35° E 36.00" AND 4" STEEL ANCHOR POST SOUTH 30.05'

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND 1/2" PIPE, WITNESSED BY:
SET NAIL & TAG #28414 SOUTH SIDE 36" BITTERNUT N 76° W 122.51'
SET NAIL & TAG #28414 NORTHEAST SIDE MAPLE S 44° E 36.63'
SET NAIL & TAG #28414 NORTHEAST SIDE OAK S 64° E 63.79'
CENTERLINE OF 4" DIAMETER STEEL ANCHOR POST S 04° E 30.05'



Signed by Maurice H. Mahieu

Date 11-20-93

Surveyor's Michigan License No. 28414

2561

P.A. 345 INGHAM COUNTY
PEER APPROVED 10/20/93

3. CORNER WAS SHOWN ON A NOV. 1874 SURVEY BY T. J. BROWN RECORDED IN LIBER 3, PAGE 90 OF COUNTY SURVEYORS RECORDS. CORNER IS A POST WITNESSED BY: LYNN 11" S $67\frac{1}{2}^{\circ}$ E 9 LKS
BEECH 20" N $3\frac{3}{4}^{\circ}$ E 4 LKS
4. CORNER WAS USED IN DEC. 19, 1899 BY JOHN MCCLEARY, SURVEYOR IN VOL. 4, PAGE 34 & 35 COUNTY SURVEY RECORDS. CORNER MONUMENTATION IS AN IRON WITNESSED BY ELM 8" N $60\frac{1}{2}^{\circ}$ W 195 LKS.
5. CORNER WAS USED BY E. A. CALKINS, COUNTY SURVEYOR ON FEB. 18, 1901 RECORDED IN FOLDER 1, PAGE 36 INGHAM COUNTY SURVEY RECORDS. MONUMENTATION WAS AN IRON WITNESSED BY:
ELM 8" N 60° W 193 LKS
BEECH 20" N $3\frac{3}{4}^{\circ}$ E 141 LKS
6. CORNER WAS RECORDED IN LCRC LIBER 2, PAGE 187 BY FRED M. WHITE (P.S. #12034) ON NOV. 20, 1972. CORNER AS NOTED IN SECTION B AS "FOUND 1/2" PIPE 1" BELOW GRAVEL SURFACE ON FENCE LINES NORTH AND SOUTH. VERIFIED BY ADJOINING CORNERS AND LINES."
1/2" PIPE WITNESSED BY: NAIL & TAG NORTH SIDE 15" MAPLE S 35° E 36.0'
CENTERLINE 4" STEEL ANCHOR POST NORTH 36.60'
CENTERLINE 4" STEEL ANCHOR POST SOUTH 30.05'
7. CORNER WAS SHOWN ON A CERTIFIED BOUNDARY SURVEY IN LIBER 1, PAGE 1000, INGHAM COUNTY RECORDS BY RONNIE M. LESTER (P.S. #18998) DATED OCT. 29, 1973. MONUMENTATION WAS NOT NOTED AND WITNESSES WERE SAME AS A-6, ABOVE.
8. CORNER WAS SHOWN ON A SURVEY RECORDED IN LIBER 2, PAGE 43, INGHAM COUNTY RECORDS BY OSCAR BOSS (P.S. #13574) ON JULY 17, 1974. CORNER MONUMENTATION WAS A 1/2" IRON FOUND, WITNESSED BY: S 35° E 36' N/S 16" MAPLE
NORTH 36.60' STEEL 4" POST
SOUTH 30.05' STEEL 4" POST
9. CORNER WAS SHOWN ON A CERTIFIED BOUNDARY SURVEY RECORDED IN LIBER 6, PAGE 329 BY LARRY BRYAN (P.S. #25832) ON AUG. 15, 1988. MONUMENTATION WAS "FOUND 1/2" PIPE CENTERLINE OF FROST ROAD ON FENCE LINE SOUTH.
SET NAIL & TAG #25832 WEST SIDE POWER POLE SOUTH 56.20'
SET NAIL & TAG #25832 SOUTH SIDE 30" HICKORY N 80° W 122.40
CENTERLINE OF 4" STEEL FENCE POST SOUTH 30.05'