

DEC 14 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 8 PAGE 53
FILED

or corners in

INGHAM <small>(County)</small>	Located In:	Corner Code //
Public Land Survey	T 3N R 1E	H-9
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Nov 24 9 04 AM '93

REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MICH.

Register of Deeds Stamp & File Number

1. Lot No. _____, Recorded Plat _____
2. Private Claims _____

WHEATFIELD

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

MAURICE H. MAHIEU, in a field survey on SEPTEMBER 20, 19 93, to hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules theretofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

1. Description of original monument and accessories and/or subsequent restoration:

1. ORIGINAL CORNER WAS SET IN MARCH 1826 BY JOSEPH WAMPLER AS A POST AND WITNESSED BY:

ELM 6" N 5° E 9 LKS
HICKORY 7" S 44 1/2° E 25 LKS

2. CORNER WAS NOTED IN A SURVEY BY A. JACKSON, SURVEYOR ON MARCH 1856 AS NOTED IN VOLUME 3, PAGE 105. NO MONUMENTATION WAS NOTED. WITNESSES ARE:

ELM 6" N 5° E 9 LKS
HICKORY 7" N 86 1/2° E 42 1/2 LKS
(CONTINUED ON BACK)

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" PIPE IN MONUMENT BOX IN CENTERLINE OF FROST ROAD AND ZIMMER ROAD. ALSO FOUND "POLARIS SURVEYING" TAG IN POWER POLE SW 74.20 FEET. REMOVED 1/2" PIPE AND DUG DOWN 3 FEET IN MONUMENT BOX AND DID NOT FIND ANY OTHER MONUMENTATION. SET 3/4" BY 24" SOLID STEEL BAR WITH TAG #28414 IN POSITION OF 1/2" PIPE. CHECKED WITH INGHAM COUNTY ROAD COMMISSION. THEIR RECORDS SHOWS CUTTING OF ROAD SURFACE OVER THE YEARS OF MAINTENANCE. NO OTHER EVIDENCE OF FORMER MONUMENTATION WAS FOUND AND CONSIDERED THE POSITION OF 3/4" ROD AS THE CORRECT POSITION.

4. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" x 24" SMOOTH STEEL ROD, WITNESSED BY:
SET NAIL AND TAG #28414 NORTH SIDE POWER POLE S 52° W 74.29 FEET
TOP OF CENTER OF 12" CMP S 78° W 79.74 FEET
TOP OF CENTER OF 10" x 12" GENERAL TELEPHONE CABLE BOX N 35° E 73.94 FEET
TOP OF CENTER OF 18" CMP S 7° E 209.30 FEET



Signed by *Maurice H. Mahieu* Date 11-22-93

Surveyor's Michigan License No. 28414

2567

3. CORNER WAS NOTED AS A STONE ON A SURVEY BY JOHN MCCREARY IN 1899 IN VOLUME 3, PAGE 215, COUNTY SURVEYOR'S RECQDS, WITNESSED BY: B. WALNUT 16 N 85 1/2° E 118
4. AN ACT 132 SURVEY IN LIBER 1, PAGE 861 BY RONNIE LESTER (P.S. #18998) SHOWS CORNER AS FOUND 1/2" PIPE. SURVEY WAS DATED JUNE 12, 1973. WITNESSES WERE:
CENTER OF TOP OF STEEL FENCE POST SE 39.68 FEET
NAIL AND TAG IN NORTH SIDE POWER POLE SW 74.20 FEET
NAIL AND TAG IN NW SIDE POWER POLE NE 40.25 FEET
5. AN ACT 132 SURVEY IN LIBER 1, PAGE 1192 BY RONNIE LESTER (P.S. #18998) DATED JUNE 12, 1993 USES SAME MONUMENTATION AND WITNESSES AS A-4.
6. AN LCRC LIBER 3, PAGE 71 DATED APRIL 7, 1974 BY RONNIE LESTER USES SAME MONUMENTATION AND WITNESSES AS A-4.
7. INGHAM COUNTY REMONUMENTATION PROGRAM OF 1978 CALLS CORNER AS FOUND 1/2" PIPE AND WITNESSED AS A TRAVERSE POINT:
CENTER OF TOP OF STEEL FENCE POST S 50° E 39.68 FEET
CENTER OF TOP OF STEEL FENCE POST S 50° W 37.75 FEET
FOUND NAIL AND TAG ON NORTH SIDE OF POWER POLE S 47° W 74.20 FEET