

DEC 14 1993

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

LIBER 8 PAGE 40  
FILED

Nov 24 9 02 AM '93

REGISTER OF DEEDS  
INGHAM COUNTY, MICH.

Register of Deeds Stamp & File Number

For corners in

INGHAM Located In: Corner Code: J-10  
(County)

- 1. Public Land Survey T 3N R 1E J-10
- 2. Property Controlling in Section S T R
- 3. Miscellaneous Property in Sec. S T R
- 4. Lot No. , Recorded Plat
- 5. Private Claims

WHEATFIELD

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, MAURICE H. MAHIEU, in a field survey on OCTOBER 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. NO CORNER WAS SET DURING THE ORIGINAL GOVERNMENT SURVEY.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

THERE IS NO HISTORY OF THIS CORNER EVER BEING SET OR USED ON PUBLIC RECORD. SET 3/4" BY 24" SOLID STEEL BAR WITH CAP #28414 AT INTERSECTION OF LINES BETWEEN 1/4 CORNERS. FENCE LINE RUNNING EAST, WEST AND SOUTH IS 17 FEET NORTH AND 5.8 FEET EAST OF SET BAR.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" BY 24" SOLID STEEL BAR WITH CAP #28414, WITNESSED BY:  
SET NAIL AND TAG #28414 NORTH SIDE 20" MAPLE N 9° W 15.08'  
SET NAIL AND TAG #28414 NORTH SIDE 12" ASH N 76° W 18.6'  
SET NAIL AND TAG #28414 SOUTH SIDE 12" HICKORY N 19° W 31.18'  
CENTER OF 4" DIAMETER METAL POST N 45° E 25.36'



Signed by Maurice H. Mahieu Date 11-22-93  
Surveyor's Michigan License No. 28414

2500

P.A. 345 INGHAM COUNTY  
PEER APPROVED vlslslsl.w