

NOV 3 1993

Nov 3 10 48 AM '93

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTER OF DEEDS
INGHAM COUNTY MICH.

For corners in

INGHAM <small>(County)</small>	Located In:	Corner Code ://
1. Public Land Survey	T <u>3N</u> R <u>1E</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

WHEATFIELD

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MAURICE H. MAHIEU, in a field survey on OCTOBER 1, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. ORIGINAL MONUMENT WAS POST SET IN ORIGINAL GOVERNMENT SURVEY BY JOSEPH WAMPLER D.S. IN FEBRUARY/MARCH 1826, WITNESSED BY: 30" BEECH S52° W 26 LKS
6" DO. N47° W 10 1/2 LKS
2. CORNER IDENTIFIED AS A 1 1/2" IRON BY THE INGHAM COUNTY ROAD COMMISSION REVISED GRID MAP DATED JANUARY 1, 1969 WITH WITNESSES: CONCRETE ANCHOR POST NW 38.35'
18" ELM WNW 40.4'
CONCRETE ANCHOR POST SW 37.35'

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 4" DIAMETER CONCRETE MONUMENT WITH 1/2" IRON ROD WITH CAP, CAP NUMBER IS NOT READABLE. FOUND 4 OF R. LESTER'S WITNESSES AS RECORDED IN LIBER 5, PAGE 78, DISTANCES MEASURED ARE IN CLOSE ACCORD WITH L.C.R.C. THE MONUMENT IS ASSUMED TO BE SAME AS A-3, AND IS THE BEST LOCATION FOR CORNER. MONUMENT IS ON CENTERLINE OF WILLIAMSTON ROAD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" CONCRETE MONUMENT LEFT IN PLACE AND WITNESSED BY:

- SET NAIL AND TAG #28414 EAST SIDE 32" MAPLE S 20° E 161.81'
- SET NAIL AND TAG #28414 WEST SIDE 24" MAPLE S 10° E 200.66'
- SET NAIL AND TAG #28414 WEST SIDE 32" MAPLE S 15° E 219.40'
- SET NAIL AND TAG #28414 SOUTH SIDE UTILITY POLE S 89° E 251.26'
- SET NAIL AND TAG #28414 SOUTH SIDE WOOD CORNER POST WEST 45.04'
- TOP CENTER G.T.E. TELEPHONE BOX N 04° E 320.44'



Signed by Maurice H. Mahieu
Surveyor's Michigan License No. 28414

Date 10-28-93

2542

3. CORNER HAS BEEN RECORDED IN L.C.R.C. LIBER 5, PAGE 78 BY RONNIE M. LESTER (PS #18998) ON NOVEMBER 30, 1978. NARRATIVE UNDER SECTION B OF L.C.R.C. STATES "EXCAVATED A HOLE 6' x 5' TO AN AVERAGE DEPTH OF 1.5' ON THE CENTERLINE OF WILLIAMSTON ROAD AND ON FENCE LINE TO THE WEST. FOUND 2 BOAT SPIKES, ONE AT THE SURFACE AND ONE 0.2' BELOW THE SURFACE, ON CENTERLINE OF WILLIAMSTON ROAD AND ON FENCE LINE TO THE WEST. FOUND OLD WOOD STAKE SURROUNDED BY TILE, THE TOP BEING 2' DEEP IN CLAY, ON THE CENTERLINE OF WILLIAMSTON ROAD, AND ON THE EXTENDED FENCE LINE TO THE WEST. ACCEPTED WOODEN STAKE AS CORNER". A 4" x 36" CONCRETE MONUMENT WITH A 1/2" x 38" REROD AND CAP #18998 WAS SET IN LOCATION OF WOODEN STAKE AND WITNESSED BY:

NAIL AND TAG #18998 NORTHEAST SIDE 6" PINE WNW 31.59'
NAIL AND TAG #18998 NORTHSIDE 8" SQUARE WOOD FENCE POST WEST 45.53'
NAIL AND TAG #18998 NORTHEAST SIDE 24" MAPLE SE 161.92'
NAIL AND TAG #18998 WEST SIDE 20" MAPLE SSE 200.73'