

DEC 14 1993

LIBER 8 PAGE 55

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

FILED

For corners in

INGHAM Located In: \_\_\_\_\_ Corner Code 11  
(County)

1. Public Land Survey T 3N R 1E K-11  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_  
 T \_\_\_\_\_ R \_\_\_\_\_

2. Property Controlling S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
 Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_

5. Private Claims \_\_\_\_\_

Nov 30 10 39 AM '93

REGISTER OF DEEDS  
*Robert G. Johnson*  
 INGHAM COUNTY, MICH.

Register of Deeds Stamp & File Number

WHEATFIELD

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, MAURICE H. MAHIEU, in a field survey on OCTOBER 29, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. ORIGINAL CORNER WAS SET IN 1826 BY JOSEPH WAMPLER WITNESSED BY:

Ash 6in N48E 18 LKS  
 Beech 16" N28W 20"

2. CORNER WAS USED MAY 9, 1884 BY G. E. STATES, COUNTY SURVEYOR. MONUMENTATION WAS A STONE WITNESSED BY: SCHOOL HOUSE S 51° 20' E 199 1/2 LKS  
 APPLE 6" S 18° W 107 LKS  
 SURVEY IN VOL. 3, PAGE 198

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 2 BOATSPIKES WITHIN 6 INCHES OF EACH OTHER IN THE INTERSECTION OF CENTERLINES OF WILLIAMSTON AND DENNIS ROAD AT ROAD SURFACE. THE UTILITY POLE WITNESS OF A-4 IS GONE. MAPLE TREE OF A-4 WAS FOUND. SCHOOL HOUSE OF A-2 AND A-3 IS STILL IN PLACE. APPLE TREE OF A-2, 3 & 6 IS GONE. MEASUREMENT FROM SCHOOL HOUSE TO FOUND BOATSPIKE WAS 128.55 FEET, OVER 3 FEET SHORT OF PREVIOUS WITNESS. REMOVED SPIKES AND DUG DOWN TO OLD ROAD SURFACE AND THEN THROUGH OLD ROAD SURFACE TO 1 FOOT BELOW OLD PAVEMENT. NO MONUMENTATION FOUND. DUG AT INTERSECTION OF CENTERLINE OF WILLIAMSTON ROAD A DISTANCE OF 131.7 FEET TO CORNER OF SCHOOL HOUSE AS PREVIOUSLY WITNESSED. HOLE WAS APPROXIMATELY 3 FEET WIDE BY 3 FEET LONG BY 3 FOOT DEEP. NO MONUMENTATION FOUND. ALSO DUG AT LOCATION WHERE A MAGNETIC PULL WAS STRONG AT APPROXIMATELY 131.7 FEET FROM SCHOOL HOUSE AND APPROXIMATELY 2 FEET WEST OF CENTERLINE OF WILLIAMSTON ROAD. DUG 2 FOOT WIDE BY 2 FOOT LONG BY 3 FOOT DEEP. NO MONUMENTATION. DECIDED CORNER WAS OBLITERATED DURING PREVIOUS ROAD WORK. SET 3/4" x 24" SOLID STEEL ROD AT INTERSECTION OF 131.7 FOOT PULL FROM SCHOOL WITH EXTENSION OF EAST SECTION LINE BETWEEN NORTHEAST CORNER AND EAST 1/4 CORNER OF SECTION 26.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET 3/4" x 24" SOLID STEEL ROD WITNESSED BY:  
 SET NAIL AND TAG #28414 WEST SIDE 32" MAPLE S 25° E 84.2 FEET  
 SET NAIL AND TAG #28414 WEST SIDE 24" MAPLE S 15° E 112.72 FEET  
 SET NAIL AND TAG #28414 SOUTH SIDE TELEPHONE POLE N 45° E 38.45 FEET  
 N.W. CORNER SCHOOL HOUSE FOUNDATION S 45° E 131.7 FEET  
 TOP OF CENTER OF GENERAL TELEPHONE CABLE BOX N 50° W 40.6 FEET  
 FOUND BOAT SPIKE SOUTH 6.58' AND WEST 1.58'



Signed by Maurice H. Mahieu Date 11-22-93  
 Surveyor's Michigan License No. 28414

3. THE INGHAM COUNTY ROAD COMMISSION SHOWS ON THEIR SECTION CORNER SHEET OF 1969 IRON, WITNESSED BY: SCHOOL HOUSE 131.7 FEET  
14" APPLE S 5° W 70.6 FEET
4. MARV FOUTY (P.S. 18989) FOUND A BOAT SPIKE PER HIS P.A. 132 SURVEY DATED 6-4-77 RECORDED IN LIBER 3, PAGE 204 AND WITNESSED BY:  
TAG WEST SIDE 30" MAPLE S 5° E 77.72 FEET  
P.K. NAIL S.W. SIDE UTILITY POLE SW 43.70 FEET
5. MARV FOUTY RECORDED SAME CORNER AS A-4 IN LCRC LIBER 4, PAGE 221. HE NOTES BOATSPIKE USED BY VARIOUS OTHER LOCAL SURVEYORS. DATE OF LCRC IS JUNE 30, 78.
6. THE INGHAM COUNTY REMONUMENTATION PROJECT OF 1978 REFERRED ON A MONUMENTED CORNER REPORT TO HAVE FOUND A 1/2" IRON BAR. SAME WITNESSES AS A-4.