

4. L.C.R.C. recorded in Liber 1, Page 521 by Ronnie M. Lester P.S. #18998 on May 11, 1972. "Found T-bar Centerline intersection of Sandhill & Hagadom Roads." Witnesses same as in A.3.
5. An Act 132 survey recorded in Liber 1, Page 570 by Ronnie M. Lester P.S. #18998 on January 5, 1973 shows same monumentation and witnesses as in A.3.
6. An Act 132 survey recorded in Liber 1, Page 695 by Fred N. White P.S. #12034 on April 18, 1973 referenced corner to Liber 1, Page 521. No monumentation description or witnesses on survey.
7. An Act 132 survey recorded in Liber 1, Page 696 by Fred N. White P.S. #12034 on April 18, 1973 shows that the corner falls 2644.76' from C-2. Monumentation and witnesses not given; corner referenced to Liber 1, Page 521.
8. An Act 132 survey recorded in Liber 2, Page 177 by Ronnie M. Lester P.S. #18998 on November 21, 1974 shows the same monumentation and witnesses as in A.3. Corner shown to fall 2644.83' from C-2.
9. An Act 132 survey recorded in Liber 2, Page 301 by Ronnie M. Lester P.S. #18998 on February 18, 1975 shows the same monumentation and witnesses as in A.3, and the same distance to C-2 as in A.8.
10. An Act 132 survey recorded in Liber 2, Page 795 by Ronnie M. Lester P.S. #18998 on July 13, 1976 shows same monumentation and witnesses as in A.3. Corner shown to fall 2644.82' from C-2 and 2653.04' from D-3.
11. An Act 132 survey recorded in Liber 2, Page 1114 by Ronnie M. Lester P.S. #18998 on May 23, 1977 shows same monumentation, witnesses, and record distances as in A.10.
12. An Act 132 survey recorded in Liber 3, Page 884 by Ronnie M. Lester P.S. #18998 on June 5, 1978 shows same monumentation, witnesses, and record distances as in A. 10.
13. An Act 132 survey recorded in Liber 3, Page 582 by Ronnie M. Lester P.S. #18998 on October 30, 1978 shows same monumentation and witnesses as in A.3., and same record distance to D-3 as in A. 10.
14. An Act 132 survey recorded in Liber 3, Page 853 by Ronnie M. Lester P.S. #18998 on June 5, 1979 shows same record distances and witnesses as in A. 10; no monumentation mentioned.
15. An Act 132 survey recorded in Liber 3, Page 1159 by Ronnie M. Lester P.S. #18998 on February 5, 1980 is a re-recording of the survey in Liber 2, Page 301; record distances, monumentation, and witnesses for this corner the same.
16. An Act 132 survey recorded in Liber 5, Page 998 by Ronnie M. Lester P.S. #18998 on February 15, 1989 describes monumentation as a square 1/2" bar with the following witnesses: Found nail and washer in NW side utility pole, 70° az. 90.8'. Set nail and tag in west side utility pole, 161° az. 58.7'. Northeast corner concrete porch, 225° az. 129.1'. Southwest corner brick house, 45° az. 113.0'.
17. An Act 132 survey recorded in Liber 5, Page 996 by Ronnie M. Lester P.S. #18998 on February 15, 1989; monumentation and witnesses same as in A. 16.
18. An Act 132 survey recorded in Liber 6, Page 605 by Larry Bryan P.S. #25832 on December 12, 1990 describes corner as a found T-bar with the following witnesses: Found nail and washer in power pole SSW 63.30'. Found nail and washer in power pole ENE 90.85'. Set nail and tag NE side power pole S 45° E 93.40'.
19. An Act 132 survey recorded in Liber 7, Page 701 by Ronnie M. Lester P.S.#18998 on January 2, 1996 describes the corner as a 1/2" square bar measuring 2644.29' from C-2 and having the following witnesses: Found nail and washer NW side utility pole, mag. az. 70° 90.79'. Found nail and tag #31603 W. side u.pole, mag. az. 161° 58.89'. NE corner foundation porch, mag. az. 224° 129.08'. SW corner brick house, mag. az. 44° 113.00'.
20. Ingham County Road Commission records show a T-iron at the corner (1962) measuring 2653.19' from D-3 and having the following witnesses: T.P. SSW 63.30'. T.P. NNW 72.68'. P.P. ENE 90.85'.

SURVEY &
REMONUMENTATION

DEC 6 7 1999

SECTION