



4. An Act 132 survey recorded in Liber 2, page 985, by James E. Stephens P.S. #16053 on February 22, 1977, shows same monumentation and witnesses for corner as in A.3. above.
5. An Act 132 survey recorded in Liber 3, Page 574, by James E. Stephens P.S. #16053 on October 16, 1978, has the same monumentation and witnesses as in A.3. above. Corner measured 2685.49' from D-1.
6. A L.C.R.C. recorded in Liber 5, page 177, by James E. Stephens P.S. #16053 on February 5, 1979, makes a reference to Liber 4, page 2 (A.3. above) and then states, "subsequent analysis and review of both old survey notes in my office and long-established lines of occupation in the field indicate subject corner should be reidentified 25.46 feet west of its 1977 recordation location. This certificate supercedes my previous recording for this corner. A boat spike was set on the south line of Section 32, T4N, R1W, 137.00 feet west of the SE corner of said Section 32." Witnesses: Survey tag S. side utility pole N 83° 30' E 130.28'. Survey Tag north side of utility pole S 70° 30' E 130.28'. Survey tag SE side utility pole S 54° W 59.35'.
7. An Act 132 survey recorded in Liber 3, page 838, by Ronnie M. Lester P.S. #18998 on May 2, 1979, identifies corner as a railroad spike with the following witnesses: Stephens Nail and Tag SE side utility pole SW 54.42'. Stephens Nail and Tag S side utility pole NE 136.73'. Stephens Nail and Tag N. side utility pole SE 145.60'. SE corner, Section 32, T4N, R1W, 1/2" bar in Monument Box, East 143.57'. Corner measured 2653.45' from D-1 and 2311.12 from E-2.
8. An Act 132 survey recorded in Liber 3, page 841, by Ronnie M. Lester P.S. #18998 on May 2, 1979, has same measurements, monumentation, and witnesses as in A.7. above.
9. An Act 132 survey recorded in Liber 3, page 927, by Ronnie M. Lester P.S. #18998 on July 13, 1979, has same measurements, monumentation, and witnesses as in A.7. above.
10. An Act 132 survey recorded in Liber 3, page 925, by Ronnie M. Lester P.S. #18998 on July 13, 1979, has same measurements, monumentation, and witnesses as in A.7. above.
11. An Act 132 survey recorded in Liber 3, page 1053, by Ronnie M. Lester P.S. #18998 on October 11, 1979, has same measurements, monumentation, and witnesses as in A.7. above.
12. An Act 132 survey recorded in Liber 4, page 1084, by Marvin F. Fouty P.S. #18989 on September 11, 1985, has same monumentation and witnesses as in A..7. above.
13. An Act 132 survey recorded in Liber 5, Page 27, by Maurice H. Mahieu P.S. #28414 on September 9, 1986, identifies corner as a boat spike witnessed by: Utility pole N 83° 30' E 130.28', utility pole S 70° 30' E 139.03', utility pole S 54° W 59.35'. Corner measured 2675.91' to F-1.
14. An Act 288 subdivision titled "Hulett Farms Industrial Park" recorded in Liber 44, Page 12, by David R. Lohr P.S. #30090 on November 15, 1988, shows the corner measured 2660.36' from D-1. No monumentation or witnesses given.
15. An Act 132 survey recorded in Liber 5, Page 1150 by Marvin F. Fouty P.S. #18989 on October 12, 1989, shows he used the corner. No monumentation, measurements, or witnesses given.
16. The Woodlands Condominium Survey Plan records in Liber 1833, Page 342, by Walter K. Kyes P.E. #14913 on July 12, 1990, shows same measurement to F-1 as in A.15 above. No monumentation or witnesses given.
17. I.C.R.C. plans for the 1992 Jolly Road improvements, Sheet 10, shows the corner at a distance of 143.57' from E-13, Meridian Twp., and 2653.59' from D-1, Alaiedon Twp.
18. An Act 132 survey recorded in Liber 7, Page 148, by James E. Stephens P.S. #16053 on April 13, 1994, has same monumentation and witnesses as in A.6. above. Corner measured 2675.95' from F-1.

1999-056026  
 Page: 2 of 2  
 11/04/1999 01:46P



**SURVEY &  
 REMONUMENTATION**

DEC 09 1999

SECTION