

**SURVEY &  
REMONUMENTATION**

DEC 13 1999

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in ALAIEDON TOWNSHIP

INGHAM COUNTY

Located In:

Corner Code #

1. Public Land Survey

T 3N R 1W

G-1

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

T \_\_\_\_\_ R \_\_\_\_\_

S \_\_\_\_\_ T \_\_\_\_\_

2. Property Controlling  
in Section

3. Miscellaneous  
Property in Sec.

S \_\_\_\_\_

S \_\_\_\_\_

S \_\_\_\_\_

S \_\_\_\_\_

T \_\_\_\_\_

T \_\_\_\_\_

T \_\_\_\_\_

T \_\_\_\_\_

Paula Johnson  
INGHAM COUNTY  
REGISTER OF DEEDS  
WOLVERINE ENGINEERS AND SUR

RECORDED  
CRNR 11.00

**L-9 P-529**

1999-054733



1999-054733

Page: 1 of 2

10/29/1999 09:34A

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Maurice H. Mahieu, in a field survey on September 10, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- Original corner set by Joseph Wampler D.S. on December 19, 1826 at a distance of 75.00 chains from G-3, a falling of 110 links from G-13, Meridian Twp. "Intersect N. Boundary 110 L. W of Post. Set post cor. Secs. 3 & 4 fw. Beech 10 S 61° W 6. Beech 5 S 33° E 27."
- Book 2, Page 177 of County Surveyor's Records contains a survey by A.P. Drake, County Surveyor, on October 13, 14, and 15, 1879 in which the corner was described as a stone with the following witness: "B. Walnut 14 S 78 1/2° W 213 1/3." Drake measured the corner 2304.72' from G-2.
- A L.C.R.C. recorded in Liber 3, Page 442 by James A. Porter P.S. #19003 on September 24, 1975 indicates that he "Set #4 rerod with cap @ GLO distance with the following witnesses: Nail and Tag in 6" Elm N 70° W 71.82 feet. Nail and Tag in Power Pole N 60° E 32.93 feet. Nail and Tag in Power Pole S 07° E 68.97 feet. SE Cor. Sec. 33 Iron/Mon. Box N 89° E 72.60 feet."

(Continued on Back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 24" iron form pin in a monument box in the centerline of Jolly Rd. and on a treeline South. Found Witness: SE Cor. Sec. 33, Meridian Twp. 3/4" x 24" iron form pin with a 2 1/2" diameter aluminum P.A. 345 cap # not legible in a monument box in the centerline of Jolly Rd., East 72.53'. Corner measured 2660.75' to F-1 and 2649.76' to H-1. Corner falls in a major fill section of Jolly Rd., therefore excavation of site not feasible. Accepted 3/4" x 24" iron form pin as position for corner because of its accordance to GLO distance and falling. Affixed a 2 1/2" diameter aluminum P.S. 345 cap #28414 to the 3/4" x 24" iron form pin.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

2 1/2" diameter aluminum P.A. 345 cap #28414 and 3/4" x 24" iron form pin. 3/4" x 24" iron form pin with a 2 1/2" diameter aluminum P.A. 345 cap (#not legible), SE Cor., Sec. 33, Meridian Twp., East 72.53'.  
Set Nail and Tag #28414 W. side Utility Pole S 04° E 68.16'  
Set Nail and Tag #28414 W. side Utility Pole N 48° E 40.27'  
SW Corner catchbasin at edge of asphalt N 77° E 97.99'

Signed by Maurice H. Mahieu

Date 10-21-99

Surveyor's Michigan License No. 28414



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN 20, 1971  
REVISED MAY 14, 1975

REVISED JAN, 1983  
REVISED OCT., 1995

P.A. 345 INGHAM COUNTY  
PEER APPROVED 9/21/99 m



(A. CONTINUED)

G-1 T3N, R1W

4. An Act 132 survey recorded in Liber 2, Page 506 by James A. Porter P.S. #19003 on September 24, 1975 indicates he set a 1/2" rebar and cap 2310.15' from G-2 for the corner. Witnesses same as in A.3. above.
5. An Act 132 survey recorded in Liber 2, Page 684 by James A. Porter P.S. #19003 on April 13, 1976 shows the corner at 72.60' West of G-13 Meridian Twp. Monumentation and witnesses not given.
6. An Act 132 survey recorded in Liber 2, Page 915 by James A. Porter P.S. #19003 on October 1, 1976 shows same falling as in A.5. above. Monumentation and witnesses not given.
7. An Act 132 survey recorded in Liber 2, Page 914 by James A. Porter P.S. #19003 on October 1, 1976 shows same falling as in A.5. above. Monumentation and witnesses not given.
8. An Act 132 survey recorded in Liber 4, Page 298 by Fred N. White P.S. #12034 on June 12, 1981 indicates he used the corner. No monumentation or witnesses given; corner referenced to Liber 3, Page 442. Corner measured 2661.53' from F-1.
9. An Act 132 survey recorded in Liber 8, Page 176 by Terry L. Wiegman P.S. #39100 on April 7, 1998 shows he measured the corner 2310.38' from G-2. Monumentation described as a "Fnd. 1/2" I.R." Witnesses same as in A.3. above.

SURVEY &  
REMONUMENTATION

DEC 09 1999

SECTION