

NOV 15 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUL 6 8 14 AM '94

COMMISSION
For corners in

REGISTER OF DEEDS
INGHAM COUNTY, MICH.

INGHAM (County)	Located In:	Corner Code #7
ALAIEDON TOWNSHIP	T 3N R 1W	G-10
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Properly Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property In Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	5		5		4		3		2				
3													
4	7		8		9		10		11		12		
5													
6	16		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		30		
13													

I, DAVID R. LOHR in a field survey on APRIL 20 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

G-10

1. POST SET BY MUSGROVE EVANS IN DECEMBER 1826, WITNESSED BY BEECH 10" SOUTH 66 DEGREES EAST, 17 LINKS (11.22') WHITE ASH 6" NORTH 73 1/2 DEGREES WEST, 28 LINKS (18.48')

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

G-10

FD. 1/2" IRON/ CAP #2585 AS PER LCRC LIBER 6-PG.153. EXCAVATED AREA 3' X 3' X 1.5' DEEP AND FOUND FLAT STONE 1.3' X 1.5' X 0.5' LYING FLAT ON SOUTH SIDE OF 1/2" IRON, WITH A PORTION OF OLD ANCHOR POST NEARBY. MEASURED 2656.42' TO G-9, RECORDED BY DRAKE TO BE 2656.5' IRON IS ON LINE BETWEEN G-9 AND G-11. ACCEPTED LOCATION OF 1/2" IRON AS CORNER AND SET 3/4" X 24" STANDARD REMON. IRON / P.A. #345 CAP #30090 SURROUNDED BY PILE OF FIELD STONES IN LOCATION OF 1/2" IRON.

C. Description of monument for corner and accessories established to perpetuate localing the position of the corner:

G-10:

SET 3/4" X 24" STANDARD RENON. BAR/P.A.#345 CAP #30090, WITNESSED BY:
 SET N&T #30090 IN N/S 8" ELM, AZ. 95 DEG. 105.82'
 SET N&T #30090 IN N/S 20" ELM, AZ. 121 DEG. 103.94'
 SET N&T #30090 IN W/S 8" BASS, AZ. 138 DEG. 91.89'
 SET N&T #30090 IN N/S 3" ELM, AZ. 264 DEG. 19.40'
 BEARING AND DISTANCE TO G-9 AZ. 00-00-00 2656.42'
 BEARING AND DISTANCE TO H-10 AZ. 90-39-34 2676.34'
 BEARING AND DISTANCE TO G-11 AZ. 180-00-03 2665.46'



Signed by David R. Lohr

Date JUNE 28, 1994

Surveyor's Michigan License No. 30090

Page 2

G-10 CONTINUED

2. UNRECORDED SURVEY IN MISC. FIELD NOTES, PAGE 23, SURVEYOR UNKNOWN, DATE UNKNOWN, NO MENTION OF MONUMENT, SAME WITNESSES AS ITEM #1.
 3. RECORDED SURVEY BY A. JACKSON, 1856, VOL. 2. PG. 285, SAME WITNESSES AS ITEM #1.
 4. "POST" FOUND BY A.P. DRAKE IN 1877 IN SURVEY RECORDED IN VOLUME 3, PAGE 25. WITNESSED BY:
BEECH 20" NORTH 8 1/2 DEGREES WEST, 27 1/4 LINKS (17.99')
BEECH 5" NORTH 84 1/2 DEGREES EAST 71 3/4 LINKS (47.36')
 5. RECORDED SURVEY A.P. DRAKE, MAY 21, 1877, VOLUME 3, PAGE 132, "STONE", WITNESSED BY:
8" ELM NORTH 68 DEGREES SOUTH 37 LINKS (24.42')
SHOWS DISTANCE TO G-9 OF 40.250 CH. (2656.5')
 6. NO OTHER REFERENCES FOUND IN COUNTY SURVEYORS RECORDS
 7. RECORDED SURVEY BY JOHN SELLEK, P.S. #2585, DATED 4/18/80. LIBER 4-PAGE 240, SET 1/2 " IRON AND CAP, WITNESSED BY:
PK NAIL 4" TWIN ELM, WEST, 19.40'
PK NAIL 3" THORNAPPLE, NORTH, 12.85'
PK NAIL 18" ELM SOUTH 65 DEGREES EAST, 104.40'
- NOTE: SURVEY NOTES THIS CORNER AS THE "E 1/4 COR, SEC. 27", HOWEVER, IT SHOULD BE NOTED AS THE "W 1/4 COR, SEC 27.")
8. L.C.R.C BY JOHN SELLEK, DATED 2/19/81, LIBER 6, PAGE 153.
"FOUND ROTTED BASE OF FENCE CORNER POST SURROUNDED BY CIRCLE OF STONES, REMAINS OF FENCE TO NORTH AND WEST.
SAME WITNESSES AS ITEM #7 ABOVE