

**SURVEY & REMONUMENTATION**

**JAN 18 2001**

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in ALAIEDON TOWNSHIP

INGHAM COUNTY

Located In:

Corner Code #

- 1. Public Land Survey      T 3N R 1W  
                                         T \_\_\_ R \_\_\_  
                                         T \_\_\_ R \_\_\_  
                                         T \_\_\_ R \_\_\_
- 2. Property Controlling    S \_\_\_ T \_\_\_ R \_\_\_  
   in Section                S \_\_\_ T \_\_\_ R \_\_\_
- 3. Miscellaneous            S \_\_\_ T \_\_\_ R \_\_\_  
   Property in Sec.        S \_\_\_ T \_\_\_ R \_\_\_

H-1  
— Paula Johnson  
— INGHAM COUNTY  
— REGISTER OF DEEDS  
— WOLVERINE ENGINEERS & SURVE

**L-10 P-26**

RECORDED CRNR 11.00 2000-046390



2000-046390

Page: 1 of 2

10/31/2000 01:29P

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Maurice H. Mahieu, in a field survey on May 24, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1. Corner not set in original government survey.
- 2. Found no evidence of corner being used in subsequent county surveys.
- 3. An Act 132 survey recorded in Liber 2, Page 914 by James A. Porter, R.L.S. #19003 on October 1, 1976 shows he measured the corner 2,578.86' from G-13, Meridian Twp. & 2,647.46' from G-1. Monumentation and witnesses not given.
- 4. An Act 132 survey recorded in Liber 2, Page 915 by James A. Porter R.L.S. #19003 on October 1, 1976 shows same measurements as in A.3; monumentation and witnesses not given.

(Continued On Back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 3/4" iron rod in a monument box ±2.5' north of the centerline of Jolly Road and 64.14' west of H-13, Meridian Township. Found a nail and tag #30090 in the south side of a 11" dead Elm (immediately adjacent to a Maple) N 60° E 44.86'. Also found a 9" Elm S 15° E ±29.50', not tagged. Other witnesses obliterated. Surveyor Porter in A.5 describes how he set a #4 rerod & cap on line between G-1 & I-1. Accepted the 3/4" iron as the perpetuated location for the corner, as assumed set in place of Surveyor Porter's #4 rerod & cap by Ingham County Road Commission. Affixed a 2 1/2" diameter Aluminum P.A. 345 cap #28414 to the 3/4" iron. Corner is 0.22' South of Standard Township Line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A 3/4" iron rod with a 2 1/2" diameter aluminum P.A. 345 cap #28414 in a monument box, witnessed by:  
Set Nail and Tag #28414 SE side 12" Maple, N 61° E 46.17'.  
Set Nail and Tag #28414 South side 11" Willow, N 75° W 157.47'.  
Set Nail and Tag #28414 East side Utility Pole S 02° W 52.11'.  
3/4" Iron Rod with a 2 1/2" diameter Aluminum P.A. 345 cap #30090 in a Monument Box, East 64.14'  
Corner measures 2655.87' to I-1 and 2649.76' to G-1.

Signed by Maurice H. Mahieu  
Surveyor's Michigan License No. 28414

Date 10-25-00



(A - Continued)

5. A L.C.R.C. recorded in Liber 4, Page 218 by James A. Porter R.L.S. #19003 on June 28, 1978 states, "Original Post and Wilnesses destroyed. Set #4 rerod/cap on line between G-1 and I-1 .....". Wilnesses: Nail and Tag in 6" Elm, N 7° W 23.04'; Nail and Tag in 8" Poplar, North 31.50'; Nail and Tag in 6" Maple, N 60° E 44.89'; Nail and Tag in 6" Elm, S 15° E 29.60'.



2000-046390  
Page: 2 of 2  
10/31/2000 01:29P

**SURVEY &  
REMONUMENTATION**

**JAN 18 2001**

**SECTION**