

FILED

NOV 15 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUL 6 8 15 AM '94

COMMISSION
For corners in

INGHAM <small>(County)</small>	Located In:	Corner Code #1
ALAIEDON TOWNSHIP		
1. Public Land Survey	T <u>3N</u> R <u>1W</u>	<u>H-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

REGISTER OF DEEDS
David R. Loehr
INGHAM COUNTY, MICH.

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID R. LOHR, In a field survey on APRIL 20, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therofore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

H-10 1. CORNER NOT SET DURING ORIGINAL GOVERNMENT SURVEYS

2. CORNER REFERRED TO IN SURVEY BY A.P. DRAKE ON 3/21/1877, VOL.3, PG.25 AND VOL. 3, PG. 132. NO MENTION OF MONUMENT AND "NO TREES" SHOWN AS WITNESSES. ALSO SHOWN AS 40.44 CHAINS (2669.04') BEARING S 89 DEG. 01' E, OF WEST 1/4 CORNER. CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

H-10: VISITED LOCATION OF CORNER AND FOUND THAT 1/2" IRON WAS MISSING DUE TO "FORCE DRAIN" IMPROVEMENTS. ALL FOUR WITNESSES OF LCRC OF L.7, PG.159 WERE IN PLACE AND IN GOOD CONDITION. RE-ESTABLISHED CORNER USING RECORDED WITNESSES. SET 3/4" X 24" STANDARD REMON. BAR / P.A.345 CAP, #30090 ON EAST SIDE OF OPEN DRAIN 16' EAST OF THE WATERS EDGE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-10: SET 3/4" X 24" STANDARD REMON. BAR AND P.A. 345 CAP #30090 WITNESSED BY:

FD. N&T #28414	N/S WOOD CORNER POST	EAST	15.13'
FD. N&T #28414	SW/S SQ. WOOD POST	S 60 DEG. E	22.68'
FD. N&T #28414	SW/S SQ. WOOD POST	S 45 DEG. E	29.66'
FD. N&T #28414	W/S WOOD POST	S 15 DEG. E	64.89'
BEARING AND DISTANCE TO H-9		AZ. 00-33-50	2651.36'
BEARING AND DISTANCE TO I-10		AZ. 90-38-17	2717.23'
BEARING AND DISTANCE TO G-10		AZ. 270-39-34	2676.34'

Signed by


David R. Loehr

Date JUNE 28, 1994

Surveyor's Michigan License No. 30090

P.A. 345 INGHAM COUNTY
PEER APPROVED 6/8/94 KL

FORM APPROVED BY MICHIGAN STATE BOARD OF LAND SURVEYORS



A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2						
3											
4	7	8	9	10	11	12					
5											
6	16	17	18	15	14	13					
7											
8	19	20	21	22	23	24					
9											
10	30	29	28	27	26	25					
11											
12	31	32	33	34	35	36					
13											

3091

Page 2

H-10

3. NO OTHER REFERENCES FOUND IN COUNTY SURVEYORS RECORDS
4. RECORDED SURVEY BY JOHN SELLEK, PS #2585, DATED 4/18/80, LIBER 4, PAGE 240 AND 242. STATES, "SET 1/2" IRON AND CAP", WITNESSED BY:
TRIPLE 12" POPLAR S25W, 38.8'; 4" OAK S40W, 21.6';
WATER EDGE W 23, 6" FENCE POST W 41.8' 4" COR. FENCE POST W 46.8'
5. L.C.R.C. BY JOHN SELLEK, DATED 2/19/81, LIBER 6, PG. 153. STATES, "FOUND ROTTED FENCE CORNER POST 12" BELOW GROUND SURROUNDED BY CIRCLE OF STONES, ALSO FENCE REMNANTS, POST IN LINE WITH 1/4 CORNERS TO NORTH, SOUTH, EAST AND WEST."
"SET 1/2" IRON AND CAP IN CENTER OF ROTTED POST:" WITNESSED AS ITEM #4.
6. L.C.R.C. BY MAURICE MAHIEU, PS #28414, DATED 9/15/89, LIBER 7, PG. 159. STATES, "FOUND 1/2" IRON ROD WITH CAP #2585. THIS CERTIFICATE IS BEING RECORDED TO UPDATE THE WITNESSES. 1/2" IRON WAS LEFT IN PLACE AND WITNESSED BY:"

NAIL/TAG IN NORTH FACE OF WOOD CORNER POST EAST	15.13'
NAIL/TAG IN S.W.CORNER OF SQUARE WOOD POST S60 DEG.E	22.68'
NAIL/TAG IN S.W.CORNER OF SQUARE WOOD POST S45 DEG.E	29.66'
NAIL/TAG IN WEST FACE OF WOOD POST S15 DEG.E	64.89'
7. RECORDED SURVEY BY MAURICE MAHIEU, DATED 6/20/89, LIBER 5, PG. 1134. NO MENTION OF CORNER MONUMENT BUT WITNESSED SAME AS #6 ABOVE.