

JAN 18 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ALAIEDON TOWNSHIP

INGHAM COUNTY Located In: Corner Code #

- 1. Public Land Survey T 3N R 1W  
T R  
T R  
T R
- 2. Property Controlling S T R  
in Section S T R
- 3. Miscellaneous S T R  
Property in Sec. S T R

I-1

Paula Johnson  
INGHAM COUNTY  
REGISTER OF DEEDS  
WOLVERINE ENGINEERS & SURVE

L-10 P-28

RECORDED & SURVE CRNR 11.00  
2000-046391  
2000-046391  
Page: 1 of 2  
10/31/2000 01:29P

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

I, Maurice H. Mahieu, in a field survey on May 25, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3		2		1
3													
4	7			8			9		10		11		12
5													
6	18			17			16		15		14		13
7													
8	19			20			21		22		23		24
9													
10	30			29			28		27		26		25
11													
12	31			32			33		34		35		36
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1. Original corner set by J. Wampler D.S. on December 16, 1826 at a distance of 76.63 chains (5057.58') from I-3. "Int. N. Boundary 76 lks West of Post. Set post cor Secs 2 & 3 fw. Beech 10 S 39 E 15, Beech 20 S 57 W 35."
- 2. A L.C.R.C. recorded in Liber 1, Page 615 by Fred N. White L.S. #12034 on June 26, 1972 describes corner as a found 3/4" iron in a Monument Box in the centerline of Jolly Rd. with the following witnesses: 10" Cherry S 65° W 4.83'; 20" Maple S 05° W 34.52'.
- 3. An Act 132 survey recorded in Liber 1, Page 304 by Fred N. White L.S. #12034 on June 26, 1972 describes corner as a 3/4" pipe in Monument Box with the same witnesses as in A-2. No relevant measurements.
- 4. An Act 132 survey recorded in Liber 1, Page 1079 by Ronnie M. Lester R.L.S. #18998 on January 3, 1974 describes corner as a Found Bar in a Monument Box. Corner measured 2359.97' from I-2. Witnesses: MDSH Tag Northwest side Power Pole NE 90.54'; SE Corner Section 34, Meridian Twp., East 50.16'; MDSH Tag in East side 30" Maple South 34.56'.

(Continued On Back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1" outside diameter pipe in a Monument Box in the centerline of Jolly Rd. 50.14' West of I-13, Meridian Twp., and on a tree line South. Other witnesses obliterated. Accepted the 1" pipe as the perpetuated location for the corner, ignoring the inconsistency in monumentation descriptions of other surveyors. Affixed a 2 1/2" Aluminum P.A. 345 Cap #28414 to the 1" pipe.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A 1" outside diameter pipe with a 2 1/2" diameter Aluminum P.A. 345 Cap #28414 in a monument box, witnessed by:  
Set Nail and Tag #28414 West side 7" Hickory S 24° W 32.83'  
Set Nail and Tag #28414 SE side 9" Ash N 68° E 47.03'  
Set Nail and Tag #28414 SW side 8" Ash N 36° W 28.74'  
3/4" pipe with a P.A. 345 Cap #25832 in a Monument Box at I-13, Meridian Twp., East 50.14'

Signed by Maurice H. Mahieu Date 10-25-00  
Surveyor's Michigan License No. 28414



(A - Continued)

5. An Act 132 survey recorded in Liber 4, Page 898 by Austin C. Williams R.L.S. #21275 on August 31, 1984 shows same witnesses as in A-2.
6. An Act 132 survey recorded in Liber 4, Page 979 by Fred N. White, L.S. #12034 on February 13, 1985 references corner to Liber 1, Page 615 (A-2).
7. An Act 132 survey recorded in Liber 5, Page 288 by George M. Young, L.S. #17640 shows same monumentation and witnesses as in A-2.



2000-046391  
Page: 2 of 2  
10/31/2000 01:29P

**SURVEY &  
REMONUMENTATION**

**JAN 18 2001**

**SECTION**