

SURVEY & REMONUMENTATION

JAN 18 2001

SECTION

LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in ALAIEDON TOWNSHIP

INGHAM COUNTY Located In: Corner Code #

- | | | |
|------------------------------------|-------------------------|-----------------|
| 1. Public Land Survey | T <u>3N</u> R <u>1W</u> | _____ J-2 _____ |
| | T _____ R _____ | |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

Paula Johnson
INGHAM COUNTY
REGISTER OF DEEDS
WOLVERINE ENGINEERS & SURVE

RECORDED CRNR 11.00

L-10 P-22

2000-046388



2000-046388
Page: 1 of 2

10/31/2000 01:29P

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Maurice H. Mahieu, in a field survey on June 16, 2000, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1. Corner not set in Original Government Survey.
2. Book 3, Page 352 of the County Surveyor's Records show a survey by A. Jackson C.S. on April 27, 1854 in which the corner measured 143 rods, 20 links (2372.70') from J-1, and 158 rods, 36 links (2630.76') from J-3.
3. An Act 132 survey recorded in Liber 3, Page 914 by Larry A. Bryan L.S. #25832 on June 26, 1979 identifies corner as a Found Boat Spike at fence intersection measuring 2650.88' from J-3 and 2643.51' from I-2. Witnesses: M.D.S.H. Tag South side 10" Wild Cherry West 5.26'. Set Nail and Tag North side 16" Maple S 60° E 32.96'. Set Nail and Tag West side 8" Ash S 10° E 8.90'.
4. A L.C. R.C. recorded in Liber 5, Page 264 by Larry A. Bryan L.S. #25832 on July 19, 1979 states of the corner, "Found large rusted boat spike in base of decayed anchor post at the intersection of old fencelines to East, West, and North in swampy area in close accord with (witnesses in A-3). Measured South to 1/8 Corner 1325.44' in close accord with M.D.S.H. records and a survey by A. Jackson dated April, 1854, (V.2., P197) of the County Survey Records. Accepted Boatspike as corner identified by M.D.S.H. records as interior 1/4 of Section."

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		●		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

(Continued On Back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a Boatspike in swampy area. Found minute traces of fence North, East, and West. Found Nail and Tag #25832 South side Multi 10"-14" Maple East 36.23'. Found Nail and Tag #25832 North side 24" Maple S 60° E 32.97'. Found Nail and Tag #25832 West side 11" Ash S 10° E 8.94'. Accepted the Boatspike as the best perpetuated location for the corner based on its being at an old fence intersection and having record of it being used in a County Survey (A-2). Replaced Boatspike with a 3/4" x 24" iron form pin and a 2 1/2" diameter aluminum P.A. 345 Cap #28414.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

A 3/4" x 24" iron form pin with a 2 1/2" diameter Aluminum Cap #28414, witnessed by:
Found Nail and Tag #25832 South side Multi 10"-14" Maple East 36.23'
Found Nail and Tag #25832 North side 24" maple S 60° E 32.97'
Found Nail and Tag #25832 West side 11" Ash S 10° E 8.94'
Set Nail and Tag #28414 SE side 28" Cherry West 41.29'

Signed by Maurice H. Mahieu Date 10-25-00
Surveyor's Michigan License No. 28414



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971
REVISED MAY 14, 1975

P.A. 345 INGHAM COUNTY
PEER APPROVED 6/20/2000 M

REVISED JAN., 1983
REVISED OCT., 1995

(A - Continued)

5. An Act 132 survey recorded in Liber 6, Page 176 by Larry A. Bryan L.S. #25832 on June 7, 1990 identifies corner as a Found Boat Spike in Down Fence, North, East, & West. Corner measured 2680.32' to K-2. Measurement to J-3 same as in A-3. Witnesses: Nail and Tag #25832 South side 20" Multi-Maple East 36.20'. Nail and Tag #25832 North side 24" Maple S 60° E 32.94'. Nail and Tag #25832 West side 10" Ash S 10° E 8.94'.
6. An Act 132 survey recorded in Liber 6, Page 190 by Larry A. Bryan L.S. #25832 on June 18, 1990 shows same measurement to J-3 and monumentation as in A-3, and same witnesses as in A-5.
7. An Act 132 survey recorded in Liber 8, Page 262 by Jeffrey K. Autenrieth P.S. #31588 on July 23, 1998 shows same monumentation and measurement to J-3 as in A-3, and same witnesses as in A-5. Corner measured 2680.32' to K-2.



2000-046388
Page: 2 of 2
10/31/2000 01:29P

**SURVEY &
REMONUMENTATION**

JAN 18 2001

SECTION