

NOV 15 1994

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

JUL 6 8 16 AM '94

COMMISSION

REGISTER OF DEEDS
INGHAM COUNTY, MICH.

For corners in

INGHAM

(County)

Located in:

Corner Code #/

ALAIEDON TOWNSHIP

1. Public Land Survey	T	<u>3N</u>	R	<u>1W</u>	<u>J-10</u>	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
	T	_____	R	_____	_____	
2. Property Controlling in Section	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____
3. Miscellaneous Property in Sec.	S	_____	T	_____	R	_____
	S	_____	T	_____	R	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID R. LOHR, in a field survey on MAY 2, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
J-10

- CORNER NOT SET DURING ORIGINAL GOVERNMENT SURVEY
- NO OTHER REFERENCED FOUND IN COUNTY SURVEYORS RECORDS

CONTINUED ON BACK

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

J-10:
VISITED CORNER LOCATION AND FOUND 1/2" IRON AS PER LCRC OF LG. PG. 154. THREE OF FOUR WITNESS TREES STILL STANDING. ALSO FOUND WHAT APPEARS TO BE THE REMAINS OF AN OLD WOOD POST AND CIRCLE OF STONES 3.0 FT. EAST X 8.5 FT. SOUTH OF IRON. TRAVERSED SECTION AND DETERMINED THAT 1/2" IRON WAS WITHIN 0.50' OF TRUE CENTER POSITION. ACCEPTED 1/2" IRON AS CORNER. NO EVIDENCE COULD BE FOUND REGARDING POST/CIRCLE OF STONES TO SOUTHEAST. LEFT 1/2" IRON WITH CAP #2585 IN POSITION.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

J-10:
1/2" IRON WITH CAP #2585 AT S.E. SIDE 16" ANCHOR POST.
WITNESSED BY:
SET N&T #30090 SE/S 14" HICK., AZ. 32 DEG., 45.20'
SET N&T #30090 W/S 30" OAK, AZ. 159 DEG., 13.40'
SET N&T #30090 S/S 5" OAK, AZ. 270 DEG., 37.28'
SET N&T #30090 E/S 8" CHERRY, AZ. 322 DEG., 33.70'
BEARING AND DISTANCE TO J-9 AZ. 00-52-55 2663.79'
BEARING AND DISTANCE TO K-10 AZ. 89-52-21 2629.06'
BEARING AND DISTANCE TO J-11 AZ. 179-53-52 2644.46'
BEARING AND DISTANCE TO I-10 AZ. 269-51-25 2604.67'



Signed by David R. Lohr Date JUNE 28, 1994

Surveyor's Michigan License No. 30090

Page 2

J-10 CONTINUED:

3. L.C.R.C. BY JOHN SELLEK, PH #2585, DATED 2/19/81, L. 6, PG. 154.
"FOUND 15" FENCE POST WITH FENCE TO EAST, WEST AND SOUTH,
POST IN LINE WITH 1/4 CORNERS EAST, WEST, NORTH AND SOUTH."
"SET 1/2" IRON AND CAP AT SE EDGE OF CORNER POST."
WITNESSED BY:

5" POPLAR,	NORTH 35 DEG. EAST,	28.7'
12" SHAG BARK HICKORY,	NORTH 35 DEG. EAST,	45.2'
NAIL 4" THORNAPPLE,	NORTH 40 DEG. WEST,	25.0'
24" OAK,	SOUTH 30 DEG. EAST,	13.4'
4. RECORDED SURVEY BY JOHN SELLEK DATED 2/19/81, LIBER 4, PG. 240-243,
STATES "SET 1/2" IRON AND CAP ON SOUTHEAST EDGE 15" CORNER POST."
SAME WITNESSES AS ITEM #3.
5. NO OTHER REFERENCES TO THIS CORNER CAN BE FOUND.