

**SURVEY & REMONUMENTATION**

JAN 18 2001

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

INGHAM COUNTY Located In: Corner Code #  
(County)  
LEROY TOWNSHIP  
1. Public Land Survey T3N R2E K-9  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
T\_\_\_ R\_\_\_  
2. Property Controlling S\_\_\_ T\_\_\_ R\_\_\_  
in Section T\_\_\_ R\_\_\_  
3. Miscellaneous S\_\_\_ T\_\_\_ R\_\_\_  
Property in Sec. S\_\_\_ T\_\_\_ R\_\_\_

Paula Johnson  
INGHAM COUNTY  
REGISTER OF DEEDS  
ENGER SURVEYING

**L-10 P-67**  
RECORDED CRNR 9.00 2000-048331

2000-048331  
Page: 1 of 1  
11/14/2000 08:41A

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID L. CLIFFORD, in a field survey on AUGUST 22, 2000. Do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. ORIGINAL POST SET BY J. WAMPLER, DEPUTY SURVEYOR IN DEC 1825; SUGAR 12 S72W 6½; SUGAR 5 N82½E 16

2. A. JACKSON, COUNTY SURVEYOR, USED CORNER IN A SURVEY RECORDED IN VOLUME 2 PAGE 280, INGHAM COUNTY SURVEYOR RECORDS IN MAR. 1856 WITH NO MENTION OF MONUMENT AND SAME WITNESSES AS GLO.

3. WA ROWE, COUNTY SURVEYOR, USED CORNER IN A SURVEY PERFORMED BY J. MCCREARY, DEPUTY COUNTY SURVEYOR AND RECORDED IN VOLUME 3 PAGE 240, INGHAM COUNTY SURVEYOR RECORDS IN MAR. 1896: STONE; ASH 16 S1E 50

4. O. BOSS RLS # 13574 RECORDED CORNER IN LIBER 2 PAGE 109 IN OCT. 1972 AND USED IT IN ACT 132 SURVEYS RECORDED IN LIBER 1 PAGE 491 IN NOV. 1972, LIBER 2 PAGES 974, 975, 980, 981, 982 AND 983 IN FEB. 1977 AS A FOUND NAIL: NAIL WEST SIDE FEN COR POST, NORTH, 18.20'; NAIL, NORTH SIDE 48" MAPLE, S75°E, 114.16'; 1/2" IRON, SOUTH, 33.00'

5. A. WILLIAMS RLS #21275 USED CORNER IN AN ACT 132 SURVEY RECORDED IN LIBER 3 PAGE 254 IN MAR 1978 WITH NO MENTION OF MONUMENT OR WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND A 1/2" X 18" BAR & ILLEGIBLE CAP 3.5' NORTH OF CENTERLINE FROST ROAD ON FENCE LINE TO NORTH MATCHING BOSS'S 1 REMAINING FENCE CORNER WITNESS TO NORTH. AFTER TRAVERSE OF NW 1/4 SECTION 25 SHOWED A GOOD PROPORTIONAL RELATIONSHIP OF BAR & CAP TO MCCREARY'S 1896 SURVEY, EXCAVATED 3' DIAMETER X 3' DEEP HOLE AROUND BAR AND FOUND A VERY OLD CONCRETE NAIL BENEATH BAR AND A STONE AND CROCKERY BENEATH BAR & NAIL. ACCEPTED BAR & CAP AS CORNER AS PERPETUATED BY EVERYONE LISTED ABOVE AND REPLACED BAR & CAP WITH STANDARD BAR AND ALUMINUM PA 345 CAP AND SET MONUMENT BOX. MEASURED EAST 2671.12' (MCCREERY 2670.36') TO L-9 AND SOUTH 2671.37' TO K-10 (MCCREERY 2669.04').

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-9 T3N-R2E  
3/4" X 24" STEEL BAR AND 2 1/2" ALUMINUM CAP STAMPED PA 345 LS 25837 INGHAM COUNTY IN MONUMENT BOX  
SET NAIL & TAG #25837 IN NORTH SIDE 19" MAPLE, S79°E, 211.00'  
SET NAIL & TAG #25837 IN EAST SIDE UTILITY POLE, S02°W, 94.85'  
TOP MOST POINT OF LARGE BOULDER, S07°W, 25.87'  
CENTERLINE SE SIDE 4" SPRUCE, S44°W, 41.60'  
CENTERLINE SE SIDE 4" SPRUCE, S63°W, 61.10'

Signed by David L. Clifford

Date AUGUST 26, 2000

Surveyor's Michigan License No. 25837



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1975  
REVISED MAY 1975  
REVISED JAN, 1863  
REVISED OCT, 1995

P.A. 345 INGHAM COUNTY  
PEER APPROVED 9/7/2000 RL