

DEC 6 9 1999

SECTION

Paula Johnson
INGHAM COUNTY
REGISTER OF DEEDS
ENGINEER SURVEYING & ENGINEERING

L-9 P-483

RECORDED
CRNR 9.00

1999-050545

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

INGHAM COUNTY (County)	Located In:	Corner Code #
LERROY TOWNSHIP	T 3N R 2E	K-12
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____



1999-050545
Page: 1 of 1
10/08/1999 02:29P

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, DAVID L. CLIFFORD, in a field survey on APRIL 12, 1999 Do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4			3		2		1	
3													
4	7		8		9			10		11		12	
5													
6	18		17		16			15		14		13	
7													
8	19		20		21			22		23		24	
9													
10	30		29		28			27		26		25	
11													
12	31		32		33			34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

1. ORIGINAL POST SET BY J. WAMPLER DS IN DEC. 1825; ASH 12 S3E 17; IRONWOOD 3 N79W 7
2. J McCREARY, FORMER INGHAM COUNTY SURVEYOR, OF LIVINGSTON COUNTY USED CORNER IN A SURVEY RECORDED IN MISC. SURVEY NOTES, INGHAM COUNTY SURVEYOR RECORDS IN APRIL 1905 WITH NO MENTION OF MONUMENT OR WITNESSES;
3. RJ ROBB, COUNTY SURVEYOR, USED CORNER IN A SURVEY RECORDED IN VOLUME 3 PAGE 257 AND VOLUME 5 PAGE 48, INGHAM COUNTY SURVEYOR RECORDS IN APRIL 1907 AS AN IRON; BITTERNUT 6" S40°W 57 LKS; ELM 18" S30°E 27 LKS; ROBB ALSO HAD TIES TO K-11, K-13 AND A GAS PIPE AT THE 1/8 POST TO THE WEST.
4. DARRELL HUGHES RLS #19834 USED CORNER IN AN ACT 132 SURVEY RECORDED IN LIBER 5 PAGE 438 IN DEC. 1983 AS A FOUND 2" PIPE; NAIL IN NORTH SIDE 4" TREE, 080°, 10.08'; NAIL IN NORTH SIDE 5" MAPLE, 152°, 20.57 FT.; NAIL IN NORTH SIDE 4" TREE, 255° 10.45 FT.; NAIL IN NORTH SIDE 5" TREE, 068°, 24.59 FT.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND 5' OF 3/4" PIPE WITH ILLEGIBLE CAP LAYING ON GROUND NEXT TO APPARENT OLD FENCE CORNER. EXCAVATED 6' DIAMETER HOLE NEXT TO PIPE AND FOUND LARGE DEPOSIT OF STONE BUT NO OBVIOUS FENCE CORNER. FOUND ROBB'S GAS PIPE AT 1/8 CORNER TO WEST AND PRORATED POSITION OF CORNER BASED ON HIS TIES TO 1/8 CORNER TO WEST AND K-11 AND K-13. SET STANDARD MONUMENT IN CENTER OF DEPOSIT OF STONE. MEASURED 2676.07' TO K-11, MEASURED 2676.39' TO K-13, AND WEST 1320.62' TO 1/8 CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-12 T3N-R2E
- 3/4" X 24" BAR & 2 1/2" ALUMINUM CAP STAMPED PA 345 25837 INGHAM COUNTY (NO NATURAL WITNESSES AVAILABLE)
- RAILROAD RAIL AT K-11, N04°32'39"W, 2676.07'
- 4" CONCRETE MONUMENT WITH 2 1/2" ALUMINUM CAP AT K-13, S04°33'35"E, 2676.39'
- 1/2" BAR WITH 2 1/2" ALUMINUM CAP IN 3" CONCRETE BASE AT L-12, N88°55'38"E, 2617.30'
- 1 1/4" GAS PIPE AT NW CORNER, EAST 1/2, SE 1/4 SECTION 35, N89°34'00"W, 1320.63'



Signed by David L. Clifford
Surveyor's Michigan License No. 25837

Date JUNE 15, 1999

P.A. 345 INGHAM COUNTY
PEER APPROVED 6/15/99 AL