

# SURVEY & REMONIMENTATION

JAN 18 2001

## SECTION

### LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>INGHAM COUNTY</u>	Located In:	Corner Code #	
(County)			
<u>LEROY TOWNSHIP</u>	<u>T 3N R 2E</u>	<u>M-6</u>	<u>Paula Johnson</u>
1. Public Land Survey	T ___ R ___	_____	INGHAM COUNTY
	T ___ R ___	_____	REGISTER OF DEEDS
	T ___ R ___	_____	REGISTER SURVEYING
2. Property Controlling in Section	S ___ T ___ R ___	_____	RECORDED
	S ___ T ___ R ___	_____	CRNR 9.00
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____	<b>L-10 P-58</b>
	S ___ T ___ R ___	_____	2000-048322

L-10 P-58

2000-048322

Page: 1 of 1  
11/14/2000 08:41A

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, DAVID L. CLIFFORD, in a field survey on AUGUST 18, 2000 Do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

**NOTE:** Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

**A. Description of original monument and accessories and/or subsequent restoration:**

1. ORIGINAL POST SET BY J. WAMPLER, DEPUTY SURVEYOR IN FEB. 1824; TAM. 8 N14E 36; TAM 8 S10W 15
2. E.N. FAIRCHILDS, SURVEYOR, USED CORNER IN A SURVEY OF COUNTY LINE ROAD RECORDED IN SURVEYORS FIELD BOOK #2 PAGE 29 IN 1857: COUNTY LINE ROAD WAS RESURVEYED BY L.D. PRESTON, COUNTY SURVEYOR, IN SEPT. 1879.
3. W. BERRYMAN, COUNTY SURVEYOR, WITNESSED CORNER IN HIS PRIVATE NOTES DATED 1960: 1/4" STEEL ROD; S80°W, 26.7' 19" WILLOW; N36°E, 38.52', 26" WILLOW; S20°E, 77.48', 24" WILLOW. CONSUMERS POWER CO. & MDSH&T RECORDS BOTH DESCRIBE CORNER THE SAME AS BERRYMAN. MDSH&T ROW MAP ALSO SHOWS CORNER TO BE 109.33' NORTH OF A-6, T3N, R3E.
4. F. WHITE, RLS # 12034, RECORDED CORNER IN LIBER 6 PAGE 112 IN NOV. 1980 AS A FOUND BOLT SPIKE 109.33' NORTH OF WEST 1/4 CORNER SECTION 7, T3N, R3E: N30°E, 42.28', N&T TOP OF GUARD RAIL POST; N28°E, 47.81' N&T TOP OF GUARD RAIL POST; N26°E, 53.60', N&T TOP OF GUARD RAIL POST; N25°W, 48.88', N&T TOP OF GUARD RAIL POST.
5. L. BRYAN, LLS 25832, USED CORNER IN AN ACT 132 SURVEY RECORDED IN LIBER 6 PAGE 575 IN DEC. 1990 WITH SAME MONUMENT & WITNESSES AS IN ITEM 4 ABOVE.
6. M. FOUTY, LLS 18989, USED CORNER IN AN ACT 132 SURVEY RECORDED IN LIBER 6 PAGE 815 IN JAN. 1991 WITH SAME MONUMENT & WITNESSES AS IN ITEM 4 ABOVE.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

SEARCHED AT APPARENT LOCATION OF CORNER AND FOUND A 1/4" BOAT SPIKE IN A 1/2" PIPE ON CENTERLINE WALLACE ROAD 109.38' NORTH OF A-6, T3N, R3E. DID NOT EXCAVATE BECAUSE OF 30' OF FILL FOR I-96 OVERPASS. ACCEPTED SPIKE AND 1/2" PIPE AS PERPETUATION OF CORNER AND REPLACED THEM WITH STANDARD BAR & ALUMINUM CAP AND SET MONUMENT BOX.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- M-6 T3N-R2E  
 3/4" BAR X 24" STEEL BAR AND 2 1/2" ALUMINUM CAP STAMPED PA 345 LS 25837 INGHAM COUNTY IN MONUMENT BOX  
 FOUND NAIL & TAG #28414 (M. MAHIEU) IN TOP GUARD RAIL POST, N36°E, 31.92'  
 FOUND NAIL & TAG #28414 IN TOP GUARD RAIL POST, S45°E, 31.92'  
 FOUND NAIL & TAG #28414 IN TOP GUARD RAIL POST, S41°W, 31.22'  
 FOUND NAIL & TAG #28414 IN TOP GUARD RAIL POST, N36°W, 32.82'  
 3/4" PIPE IN MONUMENT BOX (A-6 T3N R3E), SOUTH, 109.38'

Signed by David L. Clifford Date AUGUST 06, 2000

Surveyor's Michigan License No. 25837

FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971  
 REVISED MAY 14, 1976  
 REVISED JAN. 1983  
 REVISED OCT. 1985

P.A. 345 INGHAM COUNTY  
 PEER APPROVED 9/7/2000 *mc*

