

DEC 1 2 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 260

For corners in

INGHAM  
(County)

Located In: WILLIAMSTOWN TOWNSHIP  
Corner Code #

- 1. Public Land Survey T 4N R 1E A-12  
T      R       
T      R       
T      R
- 2. Property Controlling in Section S      T      R       
S      T      R
- 3. Miscellaneous Property in Sec. S      T      R       
S      T      R

FILED

970043434  
10/31/1997 11:07:29  
REGISTER OF DEEDS  
Paula Johnson  
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, RON HELSEL, in a field survey on OCTOBER 15 & 21, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: CORNER WAS NOT SET IN ORIGINAL GOVERNMENT SURVEY.

1) VOL 3, PAGE 229, DATED JUNE 13, 1894. COUNTY SURVEYOR W. RAYNOR WITNESSED THE CORNER BUT DID NOT IDENTIFY IT, AS: ELM 14", S70 1/2W, 162 LINKS AND ELM 10", S4 1/2W, 486 LINKS.

WITNESSED IT AS: B. THORN 5", N31E, 62 LINKS AND BITTERNUT 8", S15 1/4E, 140 LINKS

2) A L.C.R.C. WAS RECORDED IN LIBER 3, PAGE 625, BY M. DYER, P.S. NO. 21565, DATED JULY 15, 1976. HE SET A 1/2" BAR ON THE MERIDIAN AND ON A FENCE LINE TO THE EAST.

NAIL AND TAG IN SE SIDE 18" ASH, NE, 39.82' (GONE)

NAIL AND TAG IN SOUTH SIDE 15" ASH, ENE, 30.73' (GONE)

NAIL AND TAG IN U. P. SSW, 70.55' (FOUND POLE WITH J. STEPHENS TAG NO. 16053)

3) A SURVEY WAS RECORDED IN LIBER 6, PAGES 456-457, DATED SEPT. 13, 1990, BY J. STEPHENS P.S. NO. 16053 HE CALLED FOR A 1/2" BAR WITH THE SAME WITNESSES AS THE L.C.R.C. ABOVE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" BAR 1.0 FEET WEST OF CENTERLINE OF MERIDIAN ROAD WITH CAP STAMPED P.S. NO. 16053 & P.S. NO. 28414 (M. MAHIEU). EXCAVATED DOWN AND FOUND ANOTHER 1/2" REBAR ABOUT 14" BELOW. CONTINUED DIGGING TO THE OLD CLAY ROAD BED AND FOUND NO EVIDENCE OF A PREVIOUS CORNER. THE STEPHENS SURVEY RECORDED A DISTANCE OF 2647.25 FEET TO CORNER A-11. A REMON. TRAVERSE IN 1995 AND 1996 COMPUTED A DISTANCE OF 2647.35 FEET TO CORNER A-11. THE FENCE LINE TO THE EAST IS NOW GONE. ACCEPTED THE CORNER MARKER AS FAITHFUL PERPETUATION OF THE CORNER AS ESTABLISHED BY SURVEYOR DYER. SET MONUMENT BOX.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1/2" BAR AND CAP NO. 16053 AND NO. 28414, 1.0 FEET WEST OF CENTERLINE OF MERIDIAN ROAD IN MON. BOX.  
CONCRETE MONUMENT AT SOUTH R.O.W. OF SWALLOW TAIL LANE, AZ. 95°, 34.32 FEET  
CONCRETE MONUMENT AT NORTH R.O.W. OF SWALLOW TAIL LANE, AZ. 33°, 74.15 FEET  
NAIL AND TAG NO. 16053, SOUTH/SIDE POWER POLE, AZ. 210°, 70.52 FEET  
NAIL AND TAG NO. 25832, L. BRYAN P.S., WEST/SIDE 22" ASH, AZ. 20°, 115.16 FEET  
SET NAIL AND TAG NO. 18994, NORTH/SIDE TWIN 14" MULBERRY, AZ. 292°, 131.39 FEET  
EAST 344.08 FEET TO C-12  
NORTH 2647.35 FEET TO A-11  
SOUTH 2620.74 FEET TO A-13



Signed by Ron Helsel

Date OCT 27, 1997

Surveyor's Michigan License No. 18994