

DEC 16 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
WILLIAMSTOWN TOWNSHIP

Liber 9 Page 4

For corners in
INGHAM
(County)

Located In: Corner Code #

- 1. Public Land Survey T 4N R 1E C-13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____



FILED

950037632
10/01/1996 11:13:26
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	I
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, RON HELSEL, in a field survey on SEPT. 11, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL MONUMENT: POST SET BY J. WAMPLER U.S. DEPUTY SURVEYOR MARCH, 1826.
80 CHAINS FROM E-13.
BEECH 11" N61W, 35 LINKS
BEECH 15" N43 1/2E, 39 LINKS
1) COUNTY SURVEYOR W.H. RAYNER, VOL 3, PAGE 229, JUNE 13, 1894. IGNORED THIS CORNER IN HIS SURVEY AND RAN A LINE FROM D-13 (SOUTH 1/4 COR) TO A-13 (SW COR SEC. 31).

CONTINUED ON BACK

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND A 1/2" BAR AND CAP AS SET BY SURVEYOR WILLIAMS IN (2-A) ABOVE. THE POSITION OF THE BAR DID NOT CONFORM TO WILLIAMS SURVEY AND WAS NOT SET IN ACCORD WITH THE GOVERNMENT MANUAL OF PRACTICE. MEASURED 524.93' TO A-13 AND 1.5' NORTH OF THE TOWNSHIP LINE AS DETERMINED BY COUNTY SURVEYOR RAYNOR IN (1-A) ABOVE. EXCAVATED AND DID NOT FIND ANY EVIDENCE OF A PREVIOUS CORNER. DEEMED THE CORNER LOST AND SET A STANDARD 3/4" X 24" FORM PIN AT THE G.L.O. PRORATED DISTANCE BETWEEN A-13 & D-13 FOLLOWING THE INTENTION OF COUNTY SURVEYOR RAYNER. POSITION IS IN THE REMAINING REMNANTS OF AN OLD EAST-FENCE.

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
3/4" X 24" STEEL FORM PIN WITH CAP LABELED P.A. 345, P.S. NO. 18994.
SE CORNER OF GARAGE FOUNDATION, HOUSE #3560, AZ. 17°, 103.20 FEET
SW CORNER OF BRICK GARAGE FOUNDATION, HOUSE #3560, AZ. 01°, 101.13 FEET
SET NAIL AND TAG NO. 18994 NORTH/SIDE TRIPLE 12" W. CHERRY, AZ. 277°, 8.05 FEE
SET NAIL AND TAG NO. 18994 SOUTH/SIDE 10" THORNAPPLE, AZ. 98°, 43.90'
N.N.W. 1.73 FEET WILLIAMS BAR AND CAP
WEST, 525.71 FEET TO A-13 (SW COR. SEC. 31)
EAST, 2638.42 FEET TO D-13 (SOUTH 1/4 COR. SEC. 32)
WEST, 48.84 FEET TO C-1 (T3N, R1E)

Signed by Ron Helsel Date SEPT. 17, 1996

Surveyor's Michigan License No. 18994

"A" CONTINUED

2) AN UNRECORDED SURVEY, (PROVIDED BY MR. ROBERT LARKIN) BY A. WILLIAMS NO. 21275, DATED JAN./MAY 1983, CALLED FOR A CORNER SET AT THE G.L.O. DISTANCE FROM THE SW CORNER OF SECTION 31, 526.02 FEET (7.97 CHAINS). WITNESSED AS:

NAIL AND TAG N/S DOUBLE 6" WILD CHERRY, WEST 7.40' (FOUND)
NAIL AND TAG N/S 6" MAPLE WEST, 47.60' (GONE)
NAIL AND TAG N/S 10" CRABAPPLE, EAST, 54.12' (FOUND THORNAPPLE)

RECORDED
INDEXED
SERIALIZED
FEB 21 1984
FBI - MEMPHIS
FILED