

DEC 14 1993

FILED

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

DEC 3 9 25 AM '93

REGISTER OF DEEDS
INGHAM COUNTY, MICH.

For corners in
INGHAM
(County)

Located In: Corner Code #

- 1. Public Land Survey T 4N R 1E E-3
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, MARVIN FOUTY, in a field survey on AUGUST 2, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. Post set in Original Government Survey by Joseph Wampler D. S. in March 1826 with the following witnesses:
B. Oak 18 561 1/2W 51 1/2 (34.0')
W Oak 13 N 61 1/2E 62 1/2 (41.25')
- 2. County Surveyor A.P. Drake reported using the corner in a survey dated March 1879 and recorded in Volume 2, page 143 County Surveyor's Records as a set stone with no mention of witnesses.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched at probable location of the corner and found a 1/2" bar in a monument box using witnesses from A (6) and (10) above. Excavated the bottom of the monument box and at a depth of 2.5 feet found stone which seems to be lying on side or is flat. Accepted stone as corner as described by A.P. Drake in 1879. Set standard bar & cap in place of 1/2" bar on top of stone. Corner is 2.5 East of centerline Shoeman & 1.5' North of centerline Gulick on fence line to West.

Field work conducted by D. Clifford PS#25837

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Standard 3/4" X 24" Ingham County Remonumentation Bar & PA 345 Cap #18989 in Mon Box.
- Set Nail & Tag #25837 in 29" Hickory AZ 142° 53.85'
- Set Nail & Tag #25837 in Telephone Pole Anchor Post AZ 121° 53.85'
- Centerline 3" Iron Anchor Post AZ, 270°, 32.90'
- Found Nail & Tag #25832 (Bryan) in 11" Hickory AZ 261° 36.95'



Signed by Marvin Fouty Date Nov. 5, 1993
Surveyor's Michigan License No. 18989

3. Fred White LS #12034 recorded the corner on Nov. 12, 1971 in Liber 1 of corners Page 223 as a Found 1/2" Bar with the following witnesses:
24" Hickory S35°W 53.78'
4" Concrete Post West 32.92'
Street Sign N45°E 36.98'
4. Surveyor White reported using the corner on Sept. 7, 1971 and recorded in Liber 1 of Surveys Page 125 Ingham County Records and rerecorded in October 1972 in Liber 1 Page 681 as a Found 1/2" bar with the same witnesses as on his LCRC.
5. Surveyor Jim Porter LS#19003 reported using the corner on July 27, 1973 and recorded in Liber 1 of Surveys page 1139 Ingham County Records with no mention of monument or witnesses.
6. Surveyor Ron Helsel LS #18994 recorded the corner on Nov. 9, 1973 in Liber 2 of Corners page 539 as a Found 3/4" rebar with the following witnesses:
N & T W. side 27" Elm S35°E, 53.72';
N & T S. side wood anchor post Centerline 3" iron anchor post West 32.87'
7. Surveyor Ronnie Lester LS #18998 reported using the corner on March 1, 1974 and recorded in Liber 1 of surveys Page 1184 as a Found 3/4" Bar with the same witnesses as on Surveyor Helsel's LCRC.
8. Surveyor Helsel reported using the corner on March 27, 1974 and recorded in Liber 1 of Surveys Page 1173 with no mention of monument or witnesses.
9. Surveyor White reported using the corner on May 26, 1978 and recorded in Liber 3 of Surveys, page 514 with reference to Surveyor R. Helsel's LCRC.
10. Surveyor David L. Clifford LS #25837 reported using the corner on March 3, 1979 and recorded in Liber 3 of surveys with no mention of monument or witnesses:
11. Surveyor Marvin Fouty LS #18989 reported using the corner on June 28, 1987 and recorded in Liber 5 of surveys Page 575 as a Found 3/4" re-bar with the following witnesses:
Nail in 27" Elm S35°E, 53.72'
Nail in anchor post, N50°E, 40.18'
3" Iron Anchor post, West 32,87'