

SURVEY & REMONUMENTATION

LIBER 8 PAGE 378

FILED

8.15 AM '94

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

NOV 30 8 15 AM '94

REGISTER OF DEEDS
THOMAS COUNTY, MICH.

For corners in APR 10 1995

From
Williamson (County) MISSION Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>4N</u> R <u>1E</u>	<u>65</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin Fouty, in a field survey on Sept. 4, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- Post set in original Government Survey by Joseph Wanpler D.S. in March 1826 with the following witnesses:
Ash 14" N84 W 31 W. Oak 18" N42 W 33
- Surveyor Marvin Fouty LS #18989 recorded the corner on Sept. 10, 1979 in Liber 5 of Corners, Page 286 as a found 3/4" iron bar with the following witnesses: Nail & Tag in West side 38" Ash S45°W 46.34'
Nail & Tag in North side 26" Hickory S60°W 69.90' - 1/2" bar & cap N04°14'20"W 33.08'
(Continued on Back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched at probable location of the corner and found the 3/4" pipe from witnesses in item 2 above. The corner is in a fill area of approximately 5' and occupies a position with extremely poor sight distance in both directions at the bottom of a valley. Dimensions for various surveys from the corner are: Fouty W 2629.98; Bryan W2629.83'; Fouty N2650.98'; Bryan N2651.03'; Bryan E2641.32'; White S2630.92'. Accepted the pipe as the perpetuated location of the corner because any other historical evidence at the corner location was probably obliterated in the construction of the road and the current location is in agreement with historical measurements and witnesses. Replaced the pipe with standard bar and cap and monument box.. Corner is 1' North of the centerline of Haslett Road on fence line to North in 5' of Road Fill. Field work conducted by David Clifford, PS No. 25837

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Standard 3/4" x 24" Ingham County Remonumentation Bar and PA345 Cap #18989 in monument box.
- Found Nail & Tag #25832 (Bryan) in 41" Ash, AZ 238°, 46.30'
- Found Nail & Tag #25837 in 24" Hickory AZ 246°, 70.25'
- Found 1/2" bar and cap #18989 AZ 356° 33.08'
- Found Nail & Tag #25837 in SW side 13" Ash AZ 334° 29.87'



Signed by Marvin Fouty Date Oct. 30, 1994
Surveyor's Michigan License No. 18989

3. Surveyor Marvin Fouty LS # 18989 reported using the corner in a survey dated Nov. 10, 1977 and recorded in Liber 3, Page 566 with the same monument and witnesses as item 2 above.
4. Corner recorded by Fred White LS #12034 in October 1979 in Liber 5 of Corners, Page 321 as a found iron beneath bit. surface with P.K. nail at road surface witnessed by:
 - Found nail & tag: NW side 40" Oak, S40°W, 46.35'
 - Found nail & tag: North side 24" Hickory, S45°W, 69.95'
 - Found nail & tag: SW side 6" Ash, N20°W, 30.19'
5. Surveyor Larry Bryan LS # 25832 reported using the corner in a survey in 1985 (85-B-5135) as a 3/4" bar with the following witnesses:
 - Set nail & tag E. side of 8" ash N20°W 30.19'
 - Set nail & tag NW side 40" ash S40°W 46.34'
 - Found nail and tag north side 24" hickory S60°W 69.91'
6. Surveyor Bryan again reported using the corner in a survey in 1992 (92-B-36413) as a found 3/4" pipe with the following witnesses:
 - Found nail & tag #25832 in east side 8" ash, N20°W 30.20'
 - Found nail & tag #25832 in west side 40" ash S40°W 46.34'
 - Found nail & tag #18989 in north side 24" hickory S60°W 69.91'
7. Surveyor Bryan again reported using the corner in a survey in 1993 (93-B-41350) as the same monument and witnesses as in item 6. B above.