

**SURVEY &
REMONUMENTATION**

DEC 03 1999

Liber 9 Page 470

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
WILLIAMSTOWN TOWNSHIP**

SECTION

For corners in -

<u>INGHAM</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>1E</u>	<u>G-12</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED
990043533
08/26/1999 09:07:57
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, RON HELSEL, in a field survey on AUG. 3, 1999
do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL MONUMENT: POST SET BY J. WAMPLER, U.S. DEPUTY SURVEYOR, MAR. 1826. BEECH 12", N83.5W, 18.5 LINKS; BEECH 9", N56E, 13.5 LINKS
MARGIN NOTE: STONE & CROCKERY. WITNESS NOT LEGIBLE.

1) INGHAM CO. R.D COMM. GRID MAP CALLS FOR A STONE: 7" ELM NE 27.7'; 15" ELM NNW 125.1'; 3" ELM NE 34.8'; 3" ELM NW 58.8 FEET (ALL OF THESE TREES ARE NOW GONE)

2) P.A. 74 L.C.R.C, LIBER 1, PAGE 11, JUNE 2, 1971, BY CLYDE STEPHENS P.S. NO. 3829. HE FOUND A 3/4" PIPE IN THE C/L OF GLASER ROAD. WITNESSED AS: SPIKE & TAG IN 8" PINE, N75°55'W, 26.75 FEET (PINE NOW GONE); TAG IN P.POLE, N12°01'E, 73.30 FEET (POLE NOW GONE); NE CORNER FRAME HOUSE NO. 972, S65°57'W, 93.10 FEET (STILL STANDING) TOGETHER WITH A P.A. 132 SURVEY, LIBER 1, PAGE 6, DATED MAY 27, 1971, WITH SAME WITNESSES.

3) P.A. 132 SURVEY, LIBER 1, PAGES 295-296, (DATE UNREADABLE) ??, 1972, BY F.N. WHITE, P.S. NO. 12034, WITNESSED THE SAME AS ABOVE.

4) P.A. 132 SURVEY, LIBER 1, PAGES 559-560, NOV. 27, 1972, BY OSCAR BOSS, P.S. NO. 13574, "3/8" IRON FOUND"; N80W, 26.75 NAIL FD, S/S 10" EVERGREEN; S88W, 32.9, 3/4" PIPE: EAST, 45.39, NAIL N/S 12" ASH (NOW GONE)

5) P.A. 132 SURVEY, LIBER 3, PAGES 991-992, APRIL 23, 1979, G. YOUNG, P.S. NO. 17640. SAME WITNESSES AS BOSS ABOVE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1/2" REBAR 33 FEET EAST OF A BENT 3/4" PIPE AND ABOUT 4 FEET SOUTH OF A TREE ROW TO THE EAST. EXCAVATED A "T" SHAPED HOLE 7 FEET NORTH AND SOUTH AND 6 EAST AND WEST OPPOSITE THE TREE ROW TO THE WEST. DID NOT FIND ANY EVIDENCE OF A PREVIOUS CORNER. ACCEPTED THE POSITION OF THE 1/2" BAR AS FAITHFUL PERPETUATION OF THE CORNER AND SET A 3/4" X 24" STEEL FORM PIN AND STANDARD INGHAM COUNTY ALUM. DISK STAMPED P.A. 345, P.S. NO. 18994 IN THE CENTERLINE OF GLASER ROAD. AUG. 18, 1999, INFORMED BY SURVEYOR R. STEADMAN, P.S. NO. 11370 THAT KEBS INC. DID NOT HAVE ANY ADDITIONAL INFORMATION ON THE POSITION OF THIS CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" PIN AND DISK
NORTHEAST CORNER OF HOUSE NO. 972 FOUNDATION, AZ. 254°, 93.24 FEET.
NORTHEAST CORNER OF BRICK GARAGE NO. 966, AZ. 308°, 102.94 FEET.
M. FOUTY NAIL & TAG NO. 18989, NORTH/SIDE 8" PINE, AZ. 282°, 30.78 FEET.
L. BRYAN BAR & CAP NO. 25832, EAST, 33.10 FEET.
SET NAIL & TAG NO. 18994 WEST SIDE TWIN 18" ASH, AZ. 175°, 122.85 FEET.

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		16		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

Signed by Ron Helsel
Surveyor's Michigan License No. 18994

Date Aug. 21, 1999

