

**SURVEY & REMONIMENTATION**

**JAN 18 2001**

Paula Johnson  
INGHAM COUNTY  
REGISTER OF DEEDS  
RON HELSEL

**L-9 P-580**

RECORDED  
CRNR 9.00

2000-043483

**SECTION LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in **WILLIAMSTOWN TOWNSHIP**

<u>INGHAM</u> (County)	Located In:	Corner Code #
1. Public Land Survey	<u>T 4N R 1E</u>	<u>G-13</u>
	T <u>    </u> R <u>    </u>	
	T <u>    </u> R <u>    </u>	
	T <u>    </u> R <u>    </u>	
2. Property Controlling in Section	S <u>    </u> T <u>    </u> R <u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	
3. Miscellaneous Property in Sec.	S <u>    </u> T <u>    </u> R <u>    </u>	
	S <u>    </u> T <u>    </u> R <u>    </u>	



2000-043483  
Page: 1 of 1  
10/12/2000 08:08A

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, RON HELSEL, in a field survey on JULY 14, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:  
ORIGINAL MONUMENT: POST SET BY J. WAMPLER, US DEPUTY SURVEYOR, 1826 SET AT 80 CHAINS WEST OF I-13. BEECH 6", N30-1/2W, 34 LINKS; IRONWOOD 4", N64E, 15 LINKS.

- 1) DID NOT FIND ANY COUNTY SURVEYOR ACTIVITY OF PUBLIC RECORD.
- 2) INGHAM CO. RD. COM GRID MAP CALLS FOR A BLUE POINTED STONE 15" ELM, 18.6' N.; 18" OAK 28.0' N.; 8" ELM, 25.0' W.; S. LINE OF R.R. ROW 81.0' N
- 3) P.A. 74 CORNER RECORDED BY F.N. WHITE, NO. 12034, IN LIBER 1, PAGE 429, APRIL 12, 1972 "FOUND STONE AND INGHAM COUNTY ROAD COMMISSION WITNESSES, SET 1/2" IRON", R.R. R/W FENCE NORTH, 81.0'; 10" POPLAR N45°W, 41.98'; 18" ELM, N01°W, 18.88'; 15" OAK, S30°W, 18.56'.
- 4) P.A. 132 SURVEY BY FN WHITE, REC. IN LIBER 1, PAGES 295-296 SITED THE SAME MONUMENT AND WITNESSES AS ABOVE.
- 5) UNRECORDED SURVEY BY L. BRYAN NO. 25832, DATED 4-22-97, CITED "FOUND 1/2" BAR ON NORTH-SOUTH FENCE LINE 129' SOUTH OF THE CENTERLINE OF THE C&O RAILROAD." FD. NAIL & TAG #25832 EAST SIDE 16" MAPLE, S05°W, 3.24'; FD. NAIL & TAG #25832 WEST SIDE 18" OAK, S30°W, 18.51'; FD. NAIL & TAG WEST SIDE 6" OAK, N15°W, 29.49'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:  
FOUND A 1/2" IRON BAR & UNREADABLE CAP AT THE LOCATION DESCRIBED IN 2-A, 3-A, & 4-A ABOVE, IN EXISTING FENCE REMNANTS NORTH, SOUTH, & WEST. BAR WAS NEXT TO A SPLIT AND GROOVED STONE ON A TREE LINE NORTH AND SOUTH, ALSO FOUND A COILED FENCE NEARBY WHICH HAD BEEN REMOVED FROM A TREE LINE;. MEAS. NORTH 81 FEET TO THE RIGHT OF WAY FENCE REMAINS OF THE RAILROAD TO THE NORTH. FOUND ALL THREE BEARING TREES AS WITNESSED BY SURVEYOR BRYAN. THE 15" OAK S30°W, DESCRIBED BY F. WHITE & LATER WITNESSED BY L. BRYAN IS NOW A STUMP. EXCAVATED AROUND THE SPLIT AND GROOVED STONE DOWN ABOUT 2 FEET, BUT DID NOT FIND A POINTED BLUE STONE.. MEASURED WEST TO A PLOW POINT FOUND 12" DEEP AT 54.3 FEET. (GLO CALLS FOR 82 LINKS BETWEEN G-13 OF WILLIAMSTOWN TWP. & G-1 OF WHEATFIELD TOWNSHIP. ACCEPTED THE POSITION OF THE PLOW POINT AS SAID CLOSING CORNER WHICH CONFIRMED THE LOCATION OF THE 1/2" IRON BAR SET BY SURVEYOR WHITE IN 3-A ABOVE.. ACCEPTED THE 1/2" IRON BAR AS FAITHFUL PERPETUATION OF THE CORNER AND REPLACED IT WITH A STANDARD 3/4" X 24" FORM PIN AND DISK STAMPED P.A. 345, P.S. 18994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:  
3/4" BY 24" FORM PIN & INGHAM CO. STANDARD DISK. IN NORTH-SOUTH TREE ROW.  
SET NAIL & TAG #18994 ABOVE L. BRYAN N&T, W/SIDE 8" OAK, N.AZ. 01°, 29.49 FEET  
SET NAIL & TAG #18994 ABOVE L. BRYAN N&T, E/SIDE 24" MAPLE, N. AZ. 218°, 3.24 FEET  
FOUND NAIL & TAG #12034 S/SIDE 6" OAK, N. AZ. 291°, 27.70 FEET  
SET NAIL & TAG #18994 ABOVE L. BRYAN N&T, S/SIDE 18" OAK, N.AZ. 274°, 51.83 FEET  
WEST, 54.30 FEET TO G-1, WHEATFIELD TWP. T3N, R1E.

	A	B	C	D	E	F	G	H	I	J	K	L
1												
2	6		5			4		3		2		1
3												
4	7		8			9		10		11		12
5												
6	18		17			16		15		14		13
7												
8	19		20			21		22		23		24
9												
10	30		29			28		27		26		25
11												
12	31		32			33		34		35		36
13												

Signed by Ron Helsel  
Surveyor's Michigan License No. 18994

Date 9-14-00



FORM APPROVED BY MICHIGAN STATE BOARD OF PROFESSIONAL SURVEYORS, JAN. 28, 1971

P.A. 345 INGHAM COUNTY  
PEER APPROVED 9/7/2000 m

REVISED MAY 14, 1975  
REVISED JAN., 1983  
REVISED OCT., 1995