

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

CITY OF EAST LANSING - MERIDIAN TWP.

INGHAM COUNTY

Located In: Corner Code #

FILED

11/28/1995 14:13:51
REGISTER OF DEEDS
PAULA JOHNSON
INGHAM COUNTY, MI

- 1. Public Land Survey T 4N R 1W B-4
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property In Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Register of Deeds Stamp & File Number

I, Maurice H. Mahieu, in a field survey on Oct. 23, 1995 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		●		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. This corner was not set in the original government survey.
- 2. Anson Jackson, County Surveyor, recorded corner in Liber 1, Page 233, County Surveyors Records on May 12, 1848. No material noted but witnessed with: W. Oak 23 N38 1/2E 21 1/2; R. Oak 24 S55 3/4E 39 1/2.
- 3. Anson Jackson, County Surveyor, recorded corner in Liber 3, Page 114, County Surveyors Records on July 28, 1856. No material noted but witnessed with: Sugar 11 N10 2/5W 21 1/2; W. Oak 23 N58 1/2E 21 1/2; Beech 24 S58E 21 3/4.
- 4. Anson Jackson, County Surveyor, recorded corner in Liber 3, Page 117, County Surveyors Records on July 3, Page 117. No material noted but witnessed with: W. Oak 23 N58 1/2E 21 1/2; Beech 24 S75W 17

See Part A continued on back.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" concrete monument 0.45' south of East-West occupation fence line and at the south end of a occupation fence line to the north. This monument is referred to as the Southeast corner of Lot 207 and the Southwest corner of Lot 208 in the plat of Whitehills Estates No. 6 and as the interior corner of Section 7 and as the Northwest corner of Beechtree Sub. This surveyor accepts the monument as the corner based on the best location from the surrounding occupation line.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Left 4" Concrete monument in position and witnessed by:
- Face of 4" Steel fence post S05°E 8.62 feet
- Set nail and tag # 28414 east side of 12" Oak S08°W 18.24 feet
- Set nail and tag # 28414 east side of 10" Apple S28°W 6.68 feet
- Set nail and tag # 28414 east side of 8" Ash S82°W 4.92 feet



Signed by Maurice H. Mahieu Date 11/27/95
Surveyor's Michigan License No. 28414

P.A. 345 INGHAM COUNTY
PEER APPROVED: 11/21/95

P.A. 345 INGHAM COUNTY
PEER APPROVED: 11/21/95

Part A Continued

5. This corner was referred to in the following subdivisions: Whitehills Estates No. 5, Liber 18, Page 12; Whitehills Estates No. 6, Liber 21, Page 2; Whitehills Estates No. 7, Liber 23, Page 3; Whitehills Estates No. 8, Liber 24, Page 4; Beechtree Sub. Liber 33, Page 26; Rudgate Hills Liber 25, Page 5



SURVEY &
REMONUMENTATION

SEP 01 1999

SECTION