

- 7). 12-14-76 CERTIFIED BOUNDARY SURVEY (RECORDED, 9-18-77 L2, P1253, 1254 AND 1255), LAVERNE J. HENDRYX P.S. #3276 NOTES EAST 1/4 CORNER OF SECTION 23, T4N, R1W, BUT DOES NOT SHOW A MONUMENT OR WITNESSES.
- 8). 4-26-77 CERTIFIED BOUNDARY SURVEY (RECORDED, 5-23-77 L2, P1126), MARVIN F. FOUTY P.S. #18989 REPEATS THE MONUMENTATION AND WITNESSES FROM A-4.
- 9). 6-15-80 BURKE'S HILLS (RECORDED 10-6-80, LIBER 37 OF PLATS, PAGE 20), MARVIN F. FOUTY P.S. #18989 NOTES THE WEST 1/4 CORNER OF SECTION 24, T4N, R1W, WITH NO MONUMENT OR WITNESSES GIVEN, BUT SHOWS A DISTANCE OF 2646.38 FEET FROM K-8 TO K-7.
- 10). 1-12-81 CERTIFIED BOUNDARY SURVEY (RECORDED 6-18-81 L4, P314), MARVIN F. FOUTY P.S. #18989 NOTES CORNER REPEATS THE MONUMENTATION AND WITNESSES GIVEN IN A-4 AND SHOWS A DISTANCE OF 2646.38 FEET FROM K-8 TO K-7.
- 11). 7-8-87 CERTIFIED BOUNDARY SURVEY (RECORDED 9-21-90 L6, P385), LARRY A. BRYAN P.S. #25832 REPEATS MONUMENTATION FROM A-4 AND TOOK THE FOLLOWING WITNESSES: SET NAIL AND TAG NORTHEAST SIDE 12" MAPLE, S20°E 48.35 FEET. SET NAIL AND TAG SOUTH SIDE 16" ELM, N80°E 84.40 FEET. FOUND NAIL AND TAG IN WEST SIDE FENCE POST, NORTH 4.0 FEET. A DISTANCE OF 2641.39 FEET IS SHOWN FROM K-7 TO K-8 (NOTE VARIANCE WITH DISTANCES GIVEN IN A-9 AND A-10). THERE ARE TWO MONUMENTS AT THE LOCATION OF K-7. THE 1/2" BAR 3 FEET NORTH OF A 1/2" PIPE WAS ACCEPTED BY THE INGHAM COUNTY PEER REVIEW GROUP AS THE CORRECT CORNER.
- 12). 9-18-89 CERTIFIED BOUNDARY SURVEY (RECORDED 4-20-90 L6, P130), LARRY A. BRYAN P.S. #25832 REPEATS MONUMENTATION AND WITNESSES FROM A-11.
- 13). 9-24-92 WELLINGTON ESTATES (RECORDED 4-22-93, LIBER 48 OF PLATS, PAGE 11-14), LARRY A. BRYAN P.S. #25832 NOTES THE WEST 1/4 CORNER OF SECTION 24, T4N, R1W, REFERENCES A-4, SHOWS A DISTANCE OF 2646.38 FEET FROM K-8 TO K-7 AND 2644.41 FEET FROM K-8 TO K-9.
- 14). 10-1-92 CERTIFIED BOUNDARY SURVEY (RECORDED 12-29-92 L6, P1088), LARRY A. BRYAN P.S. #25832 REPEATS MONUMENTATION AND WITNESSES FROM A-4.



2000-048473
Page: 2 of 2
11/15/2000 08:16A

**SURVEY &
REMONIMENTATION**

JAN 18 2001

SECTION