

**SURVEY & REMONUMENTATION**

JAN 18 2001

**SECTION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
MERIDIAN TOWNSHIP  
INGHAM  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 4N R 1W L-6
- 2. Property Controlling S T R
- in Section S T R
- 3. Miscellaneous S T R
- Property in Sec. S T R
- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

Paula Johnson  
INGHAM COUNTY  
REGISTER OF DEEDS  
KEBS INCORPORATED

RECORDED L-10 P-85  
CRNR 11.00 2000-048471



2000-048471  
Page: 1 of 2  
11/15/2000 08:16A

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, LARRY A. BRYAN, in a field survey on MAY 2, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1). CORNER NOT SET IN ORIGINAL GOVERNMENT SURVEY.
- 2). 7-21-76 LAND CORNER RECORDATION CERTIFICATE (SIGNED 1-6-79, FILED 1-8-79 L5, P131): RICHARD W. STEADMAN P.S. #11370, PART A: THE CENTER OF THE SECTION WAS CUSTOMARILY MONUMENTED ORIGINALLY BY THE COUNTY SURVEYOR, SINCE THE INSTRUCTIONS FOR THE U.S. SURVEY OF THE PUBLIC LANDS DID NOT INCLUDE ITS ESTABLISHMENT. HOWEVER, I FIND NO SURVEYS OF THIS SECTION IN THE INGHAM COUNTY SURVEYOR'S RECORDS. PART B: THERE ARE DRAINAGE DITCHES IN THE VICINITY OF THE CENTER OF THE SECTION, THE CONSTRUCTION OF WHICH MAY HAVE BEEN DESTROYED ANY EVIDENCE OF ITS LOCATION. REESTABLISHED CENTER OF SECTION AT INTERSECTION OF THE QUARTER LINES. PART C: SET 3/4" IRON PIPE 5' LONG TO MARK THE CENTER OF THE SECTION. WITNESSES: WOOD FENCE POST, S15°W, 15.30 FT. WOOD FENCE POST, S45°W, 7.00 FT. WOOD FENCE POST, S73°W, 16.75 FT.
- 3). 7-24-76 CERTIFIED BOUNDARY SURVEY (RECORDED 7-26-76 L2, P840), RICHARD W. STEADMAN P.S. #11370, NOTES CORNER AS 3/4" IRON PIPE AND REPEATS THE WITNESSES GIVEN IN A-2 AND SHOWS A DISTANCE OF 2635.18 FEET FROM L-6 TO L-5.
- 4). 12-22-77 CERTIFIED BOUNDARY SURVEY (REVISED 2-17-78 RECORDED 1-8-79 L3, P697), RICHARD W. STEADMAN P.S. #11370, REPEATS THE MONUMENTATION AND WITNESSES GIVEN IN A-2.
- 5). 9-5-78 CERTIFIED BOUNDARY SURVEY (RECORDED 10-11-78 L3, P560), MARVIN F. FOUTY P.S. #18989 REPEATS THE MONUMENTATION AND WITNESSES GIVEN IN A-2.

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 3/4" PIPE 5 FEET LONG ABOUT 8 FEET NORTHEAST OF INTERSECTION OF FENCES TO WEST AND SOUTH. FOUND NAIL AND TAG #11370 IN NORTHEAST SIDE WOOD FENCE POST, S45°W, 7.70 FEET (7.00' A-2). FOUND NAIL AND TAG #11370 IN TOP OF WOOD FENCE POST, S73°W, 17.42 FEET (16.75' A-2). BOTH FENCE POSTS ARE LEANING OVER. ACCEPTED 3/4" PIPE AS BEST EVIDENCE OF THE CENTER OF SECTION 13, T4N, R1W, (L-6) AND LEFT IN PLACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

L-6, SET 2-1/2" ALUMINUM CAP STAMPED: "P.A. 345, 25832, INGHAM COUNTY" ON FOUND 3/4" PIPE AND TOOK THE FOLLOWING WITNESSES.

- FOUND NAIL AND TAG #11370 IN NORTHEAST SIDE WOOD FENCE POST, S45°W, 7.70 FEET.
- FOUND NAIL AND TAG #11370 IN TOP OF WOOD FENCE POST, S73°W, 17.42 FEET.
- SET NAIL AND "KEBS" TAG IN NORTH SIDE WOOD FENCE POST, S55°W, 11.42 FEET.
- SET NAIL AND "KEBS" TAG IN SOUTH SIDE 4" TWIN POPLAR, N65°W, 13.71 FEET.
- SET NAIL AND "KEBS" TAG IN SOUTH SIDE 4" TWIN POPLAR, N45°W, 11.42 FEET.

Signed by Larry A. Bryan  
Surveyor's Michigan License No. 25832

Date 10-26-00

P.A. 345 INGHAM COUNTY  
PEER APPROVED 10/03/2000 re

- 6). 10-1-79 CERTIFIED BOUNDARY SURVEY (RECORDED 6-16-81 L4, P302), MARVIN F. FOUTY P.S. #18989 REPEATS THE MONUMENTATION AND WITNESSES GIVEN IN A-2. AND SHOWS A DISTANCE OF 2624.52' FROM L-6 TO K-6.
- 7). 4-8-81 CERTIFIED BOUNDARY SURVEY (RECORDED 6-16-81 L4, P300), MARVIN F. FOUTY P.S. #18989 REPEATS THE MONUMENTATION AND WITNESSES GIVEN IN A-2 AND SHOWS A DISTANCE OF 2624.52' FROM L-6 TO K-6.
- 8). 4-14-86 CERTIFIED BOUNDARY SURVEY (NO RECORDING STAMP ON ANY PAGE, L4, P1271), RONNIE M. LESTER P.S. #18998 REPEATS THE MONUMENTATION AND WITNESSES GIVEN IN A-2. A DISTANCE OF 2635.18 FEET IS SHOWN FROM L-6 TO L-5.
- 9). 3-31-87 CERTIFIED BOUNDARY SURVEY (RECORDED 8-10-87, L5, P1269), RONNIE M. LESTER P.S. #18998 REPEATS THE MONUMENTATION AND WITNESSES FROM A-2 AND SHOWS A DISTANCE OF 2635.18 FROM L-6 TO L-5.
- 10). 7-27-88 CERTIFIED BOUNDARY SURVEY (RECORDED 8-15-90, L6, P337), LARRY A. BRYAN P.S. #25832 REPEATS THE MONUMENTATION AND WITNESSES FROM A-2 AND GIVES A DISTANCE OF 2635.04 FEET FROM L-6 TO L-5 AND 2617.60 FEET FROM L-6 TO M-6.
- 11). 3-2-94 CERTIFIED BOUNDARY SURVEY (RECORDED 11-14-95, L7, P675), TERRY L. WIEGMAN P.S. #39100 REPEATS THE MONUMENTATION AND WITNESSES FROM A-2 AND GIVES A DISTANCE OF 2633.82 FEET FROM L-6 TO L-5.
- 12). 11-8-95 CERTIFIED BOUNDARY SURVEY (RECORDED 11-14-95, L7, P672), TERRY L. WIEGMAN P.S. #39100 REPEATS THE MONUMENTATION AND WITNESSES FROM A-2 AND GIVES A DISTANCE OF 2633.82 FEET FROM L-6 TO L-5.
- 13). 12-31-98 CERTIFIED BOUNDARY SURVEY (RECORDED 1-5-99, L8, P387), TERRY L. WIEGMAN P.S. #39100 REPEATS THE MONUMENTATION AND WITNESSES FROM A-2 AND GIVES A DISTANCE OF 2633.82 FEET FROM L-6 TO L-5.
- 14). 12-31-98 CERTIFIED BOUNDARY SURVEY (RECORDED 1-5-99, L8, P389), TERRY L. WIEGMAN P.S. #39100 REPEATS THE MONUMENTATION AND WITNESSES FROM A-2 AND GIVES A DISTANCE OF 2633.82 FEET FROM L-6 TO L-5.



2000-048471  
Page: 2 of 2  
11/15/2000 08:16A

**SURVEY &  
REMONUMENTATION**

**JAN 18 2001**

**SECTION**