

FILED

LIBER 8 PAGE 368

Nov 30 8 13 AM '94

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

**INGHAM COUNTY SURVEY & REMONUMENTATION COMMISSION**  
APR 10 1995  
For corner of Ingham (County) Locke Located In: \_\_\_\_\_ Corner Code #/ # \_\_\_\_\_

REGISTER OF DEEDS  
INGHAM COUNTY, MICH.

- 1. Public Land Survey 4N R 2E Corner Code #/ # D-3
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3			●										
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Marvin Fouty, in a field survey on Sept 4, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 1. Post set in original Government Survey by Joseph Wampler D.S. in April 1826, with the following witnesses:  
W.O. 10 S31E 4-1/2  
Ash 10 N13W 3-1/2

(continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Searched at location determined by Section survey. Found concrete monument No. 18998 called for by Surveyor Lester. 2 of the Lester witnesses were intact. Measurements reported Fouty N2655.94'; Fouty E2633.14'; Bryan E2634.65'; Bryan S2602.49'; Fouty W2611.64'; Bryan W2609.43'. Lester's excavation had produced an axle shaft surrounded by clay tile. I therefore accepted his monument as the best evidence of the perpetuated location of the corner and replaced with Standard 3/4" x 24" Ingham County Remonumentation Bar and PA345 Cap #18989 in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Standard 3/4" x 24" Ingham County Remonumentation Bar and PA345 Cap #18989 in monument box.
- Nail & Tag #18998 S Side Corner Post West 16.69'
- Nail & Tag W Side Corner Post N10°W 29.62'
- Nail & Tag W Side 10" Elm S17°E 119.42'
- Nail & Tag N Side 12" Elm S80°E 142.05'
- Nail & Tag NE Side Utility Pole N70°E 48.26'
- SE Corner stone foundation of gray 2 story farmhouse East 182.32'



Signed by Marvin Fouty Date Oct. 5, 1994  
Surveyor's Michigan License No. 18989

2. Note on T.J. Brown survey dated Sept. 2, 1864 and recorded in Vol.3, Page 15, County Surveyors Records, added by A.P. Drake, County Surveyor, on May 28, 1879 "found old stumps, marked these new trees"  
Hickory 4 N82°E 110-1/2"  
W. O. 20 N54°W 92

3. Ronnie M. Lester LS# 18998 recorded corner on November 30, 1978 in Liber 5 of Corners, Page 72 Ingham Co. Records as a Found axle shaft surrounded by clay tile subsequently replaced by 4"X 36" concrete monument with 1/2"X 38" rerod with cap #18998 and the following witnesses:

Placed small dent in west end C.M.P., South 44.11'

Nail and tag #18998 South side 60" Walnut, NW, 129.01'

Nail and tag #18998 South side 5" wood Fence Post, West, 16.69'

Nail and tag #18998 South side 24" Wild Cherry, West, 201.88'

Found dent in north end C.M.P., East 52.09

SE corner stone foundation of gray 2 story farmhouse 1' above ground, East, 182.32'

4. Larry Bryan LS# 25832 reported using the corner in an unrecorded survey in March of 1991 with no record of monument or witnesses. Surveyor Bryan supplied me with his Section breakdown dimensions.