

SURVEY & REMONUMENTATION COMMISSION

APR 10 1995

LIBER 8 PAGE 370

FILED

NOV 30 8 13 AM '94

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

REGISTERED DEEDS
INGHAM COUNTY, MICH.

For corners in

Ingham County
Locke

Located In:

Corner Code #

1. Public Land Survey	T <u>4N</u> R <u>2E</u>	<u>D-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Marvin Fouty, in a field survey on Mar. 28, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	I
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5		●										
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:


1. Post set in original Government Survey by Joseph Wampler in April 1826, witnessed by:
WO 20" N43°W 69-1/2'
DO 32" S52°W 65-1/2'
2. A. Jackson, Co. Surveyor, reported using corner in survey dated June 14, 1841 and recorded in Vol. 1, Page 199 of County Surveyor's Records with no mention of monument and the following witnesses:
W. Oak 20" N43-1/2°W 69-1/2'
W. Oak 32" S52°W 65-1/2' (continued on back)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" bar in Haslett Road at Pringle. The monument set by Lester in A4 was not found. Found the hole in CMP witness from A4. The 24" maple SW 52.89' in A4 is now a stump at ground level. The 12" Oak SSE at 52.12' was still present. Measurements from the corner are Bryan W2612.33'; Fouty W2612.51'; Bryan N2641.84'; Fouty N2642.08'; Bryan E2627.22'; Fouty E2627.15'; Lester measured the Mile along the South line of Section 5 as 5238.90'; Bryan 5239.22'; and Fouty 5239.76'. I accepted the 1/2" iron bar as being the perpetuation of the corner reestablished by Surveyor Lester in A4 above. Replaced found iron with Standard 3/4" x 24" Ingham County Remonumentation Bar and PA 345 Cap #18989 in monument box.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Standard 3/4" x 24" Ingham County Remonumentation Bar and PA345 Cap #18989 in monument box.
- Set Nail & Tag #18989 in N Side 14" Oak S50°E 73.81'
- Set Nail & Tag in W side Brace Post to South 38.40'
- Set Nail & Tag in E side Power Pole N25°W 76.25'
- Found 1/4" Hole punched in top/center of E. end of 24" CMP. ENE 35.88'



Signed by Marvin Fouty
Surveyor's Michigan License No. 18989

Date Oct. 5, 1994

3. John MCreary, Co. Surveyor, reported using corner in survey dated March 19, 1890 in Vol 1, Pages 198, 199 and added witness:

W. Oak 18' S22-1/2°E 53'

4. Surveyor Ronnie M. Lester LS# 18998 as a part of the Ingham County remonumentation project recorded the corner on June 22, 1979 in Liber 5 of Corners, Page 157 Ingham Co. Records as a found pyramid of 24 stones with a 3"x8"x10" pointed stone on top. The recordation certificate filed by Surveyor Lester states "Excavated a 7' x 8' hole to an average depth of 4.9', mostly north of the centerline of Haslett Road, west of the centerline of Pringle Road and on a tree/fence line to the south. Found a pyramid of 24 stones with a 3" x 8" x 10" pointed stone as the top of the pyramid 2.5' below the surface +/- 3.0' north of centerline of Haslett Road and on tree/fence line to the south. Location of stone pile is in close accord with witnesses as given by Ingham County Road Commission records and records attributed to Wm. Barryman, County Surveyor.....". He subsequently replaced the found monument with a 4"X36" concrete monument with a 1/2"X36" rerod and cap #18998 with concrete collar and the following witnesses:

Nail and tag #18998, north side 24" Maple, S.W. 52.89'

Nail and tag #18998, north side 28" Maple, WSW, 97.30'

Nail and tag #18998, east side 12" Oak, SSE. 52.12'

1/4" hole punched in top center of 24" CMP, ENE, 35.88'

5. Larry a Bryan LS# 25832 used corner in a survey on June 3, 1987 as a found 1/2" bar and recorded in Liber 6 of Surveys, Page 416 witnessed by:

Nail and tag, North side 24" stump, Southwest, 52.89'

Nail and tag, North side 28" stump, West-Southwest, 97.30'

Nail and tag, East side 12" Oak, South-Southeast, 52.12'