

DEC 1 2 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970 Liber

9 Page 169

For corners in

INGHAM (County)

Located In: Corner Code #
LOCKE TOWNSHIP

- 1. Public Land Survey T 4N R 2E G-10
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

FILED

970022428
06/20/1997 15:33:23
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, RON HELSEL, in a field survey on APRIL 3, 1997, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

Grid table with columns A-L and rows 1-13. A dot is marked at the intersection of column G and row 10.

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration: ORIGINAL MONUMENT: POST SET BY J. WAMPLER, U.S. DEPUTY SURVEYOR, MARCH, 1826. ASH 16", N87W, 27 LINKS

- 1) VOL. 2, P. 157, COUNTY SURVEYOR A. JACKSON, AUG. 1853, CALLED FOR THE SAME BEARING TREES AS THE ORIGINAL CORNER.
2) 1969 REVISED ING. CO. ROAD COMMISSION GRID MAP CALLED FOR A 1 1/2" IRON (BRICK) ELM 5" S. 21'2" (GONE) PIGNUT 5" S70E, 88'10" (FOUND HICKORY TREE) ELM 15" S65W, 79'9" (GONE) ELM 16" N75W, 96'1" (GONE)
3) L.C.R.C. RECORDED IN LIBER 5, PAGE 158, FIELD DATED OCT. 12, 1978 BY R. LESTER P.S. NO. 18998. CETA REMON. CREW EXCAVATED A 6'X6' HOLE. "FOUND 1.5"X2.2' PIPE SURROUNDED BY BRICK, 0.3' BELOW SURFACE. SET 4"X36" CONCRETE MONUMENT WITH 1/2"X38" REROD AND CAP #18998." NAIL & TAG, #18998, NORTH SIDE 14" PIGNUT HICKORY, ESE, 88.16' (FOUND) NAIL & TAG, #18998, NORTH SIDE 8" ASH, SSE, 48.09' (FOUND) NAIL & TAG, #18998, WEST SIDE 14" WALNUT, SOUTH, 86.92' (FOUND) NAIL & TAG, #18998, SOUTHEAST SIDE 4" ELM, NNW, 21.22' (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner: FOUND A MONUMENT BOX AND 1/2" REBAR ENCASED IN A 4" CONCRETE MONUMENT 1.5 FEET NORTH OF 1/2 OF MOYER ROAD AND ON TREE AND BRUSH ROWS NORTH AND SOUTH, AS DESCRIBED IN 3-A ABOVE. LONG TIME RESIDENT, MR. ROBERT WHITE RECALLED THE CORNER AS A 2" PIPE INSIDE A BRICK CHIMNEY, IN THE LATE 1940'S. ACCEPTED THE POSITION OF THE PIPE AND THE SUBSEQUENT CONCRETE MONUMENT AS FAITHFUL PERPETUATION OF THE CORNER. SET CAP ON 1/2" REBAR STAMPED P.S. NO. 18994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner: 1/2" BAR & CONCRETE WITH CAP NO. 18994, 1.5' NORTH CENTERLINE MOYER ROAD.

- SET NAIL AND TAG NO. 18994 EAST SIDE 12" ELM, AZ., 358 DEG., 20.93 FEET
SET NAIL AND TAG NO. 18994 SE SIDE 8" ELM, AZ., 20 DEG., 20.14 FEET
SET NAIL AND TAG NO. 18994 WEST SIDE 12" ASH, AZ., 48 DEG., 28.68 FEET
SET NAIL AND TAG NO. 18994 WEST SIDE 12" TWIN ASH, AZ., 175 DEG., 48.17 FEET
FOUND NAIL AND TAG NO. 18998 WEST SIDE 16" WALNUT, AZ., 180 DEG., 86.92 FEET
SET NAIL AND TAG NO. 18994 WEST SIDE 18" PIGNUT HICKORY, AZ., 115 DEG., 88.58 FEET



Signed by Ron Helsel Date 6-7-97
Surveyor's Michigan License No. 18994