

REMONUMENT

DEC 1 8 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber

9 Page 172

FILED

For corners in

INGHAM
Code #
(County)

Located In: Corner
LOCKE TOWNSHIP

- 1. Public Land Survey T 4N R 2E H-11
 T R
 T R
 T R
- 2. Property Controlling S T R
 in Section S T R
- 3. Miscellaneous S T R
 Property in Sec. S T R

970022431
06/20/1997 15:33:30
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, RON HELSEL, in a field survey on APRIL 10, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL MONUMENT: POST SET BY JOSEPH WAMPLER, U. S. DEPUTY SURVEYOR, MARCH, 1826. BEECH 12", SOUTH 10 1/2 LINKS
SUGAR 21", S58W, 9 LINKS

1) VOL. 2, P. 157, COUNTY SURVEYOR A. JACKSON, AUG. 29, 1853, WITNESSED AS:
SUGAR, 16", S31E, 23 LINKS
MAPLE, 9", N55W, 18 3/4 LINKS

2) A L.C.R.C. WAS RECORDED IN LIBER 5, PAGE 285, DATED AUG. 3, 1979 TOGETHER WITH AN UNRECORDED SURVEY 79-B-081 OF THE SAME DATE, BY L. BRYAN P.S. NO. 25832. " EXCAVATED 6X6 HOLE TO AN AVERAGE DEPTH OF 2.0' AT INTERSECTION OF FALLEN FENCE LINES TO THE SOUTH, EAST, AND WEST BUT FOUND NO EVIDENCE OF CORNER. SET CORNER AT INTERSECTION OF FENCES, MEASURED NORTH AND EAST IN CLOSE ACCORD WITH G.L.O. DISTANCES." SET 1/2" BAR AND CAP SET NAIL AND TAG, R.L.S. #25832, WEST SIDE OF 5" OAK, S10E, 24.89' (FOUND OAK)
SET NAIL AND TAG, R.L.S. #25832, NORTH SIDE OF 24" MAPLE, S45E, 33.96' (GONE)
SET NAIL AND TAG, R.L.S. #25832, NORTH SIDE OF 6" MULTIPLE MAPLE, S75E, 54.16' (GONE)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" REBAR AT LOCATION OF DOWNED FENCES, SOUTH, EAST, AND WEST. FENCES WERE GONE ABOUT 4 FEET WEST, SOUTH, AND EAST INDICATING A PREVIOUS EXCAVATION BY SURVEYOR BRYAN. EXCAVATED AND PROBED ALONG THE FENCE REMAINS SOUTHERLY FROM THE 1/2" MARKER ABOUT 15 FEET. DID NOT FIND ANY EVIDENCE OF A PREVIOUS CORNER AND COULD NOT DISPUTE THE LOCATION OF THE EXISTING MARKER. ACCEPTED THE POSITION AND REPLACED THE 1/2" BAR WITH A 3/4" FORM PIN AND CAP STAMPED P.A. 345, P.S. NO. 18994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
3/4" FORM PIN AND CAP AT INTERSECTION OF DOWNED FENCES.

- SET NAIL AND TAG, NO. 18994 SE/SIDE 6" POPLAR, AZ., 50 DEG., 12.04 FEET
- SET NAIL AND TAG, NO. 18994 SW/SIDE 10" OAK, AZ., 135 DEG., 31.58 FEET
- SET NAIL AND TAG, NO. 18994 WEST/SIDE 8" OAK, AZ., 175 DEG., 24.91 FEET
- SET NAIL AND TAG, NO. 18994 EAST/SIDE 5" POPLAR, AZ., 210 DEG., 23.40 FEET
- SET NAIL AND TAG, NO. 18994 NORTH/SIDE 10" POPLAR, AZ., 265 DEG., 35.97 FEET

Signed by Ron Helsel
Surveyor's Michigan License No. 18994

Date 6-7-97

