

DEC 1 2 1997

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 176

For corners in

INGHAM
Code # _____
(County)

Located In: _____ Corner _____
LOCKE TOWNSHIP

- 1. Public Land Survey T 4N R 2E _____ 1-11
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, RON HELSEL, in a field survey on MARCH 26, 1997 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL MONUMENT: POST SET BY JOSEPH WAMPLER, U. S. DEPUTY SURVEYOR, MAR., 1826. WITNESSED AS: 12" BEECH, S13W, 7 LINKS
9" SUGAR, N55W, 20 LINKS

- 1) VOL. 2, PAGE 183, FEB. 3, 1854, CO. SURVEYOR A. JACKSON: BEECH, S45E, 155 LINKS, "NO OTHER TREES". A MARGINAL NOTE, ATTRIBUTED TO CO. SURVEYOR, J. McCREARY, "CORNER IS AN R.R. IRON"
- 2) VOL. 2, PAGE 276, FEB. 27, 1856, CO. SURVEYOR A. JACKSON: WITNESSED SAME AS ABOVE.
- 3) VOL. 3, PAGE 159, NOV. 18 & DEC. 2, 1879, AND LATER IN VOL. 3, PAGE 16, NOV. 25-27, 1879, CO. SURVEYOR A. P. DRAKE CALLED FOR A R.R. IRON. ELM, 10", S85E, 133 LINKS.

(CONTINUED ON BACK)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

EXCAVATED AND FOUND THE 1/2" REBAR AND A 24" SECTION OF RAILROAD RAIL AT THE LOCATION CITED BY SURVEYOR BOSS IN HIS L.C.R.C. 4-A ABOVE. SINCE THE AREA IS IN A COUNTY ROAD CUT, ACCEPTED THE POSITION OF THE RAILROAD RAIL AS A 120 YEAR PERPETUATION OF DRAKE'S SURVEY, SUPPORTED BY SURVEYOR McCREARY'S MARGINAL NOTE DATED MAR. 20 1889 IN JACKSON'S 1854 AND 1856 SURVEYS. POSITION OF CORNER IN 1/4 OF WEBBERVILLE ROAD AND ON LINE WITH A BRUSH AND TREE ROW TO THE WEST. REPLACED 1/2" REBAR WITH 3/4" FORM PIN AND CAP STAMPED P.A. 345, P.S. NO. 18894. SET MONUMENT BOX TO SURFACE OF ROAD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
3/4" FORM PIN AND CAP IN 1/4 OF WEBBERVILLE ROAD

- FOUND L. BRYAN NAIL AND TAG NO. 25832, WEST/SIDE, 8" MAPLE, AZ., 61 DEG., 25.92 FEET
- FOUND L. BRYAN NAIL AND TAG NO. 25832, NORTH/SIDE, 20" BEECH, AZ., 288 DEG., 27.22 FEET
- FOUND L. BRYAN NAIL AND TAG NO. 25832, NORTH ROOT OF 32" MAPLE, AZ., 139 DEG., 26.76 FEET
- SET NAIL AND TAG NO. 18994, NORTH/SIDE, 30" MAPLE, AZ., 250 DEG., 33.78 FEET
- SET NAIL AND TAG NO. 18994, EAST/SIDE, 18" MAPLE, AZ., 203 DEG., 83.42 FEET

FILED

970022434
06/20/1997 15:33:35
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

Signed by Ron Helsel
Surveyor's Michigan License No. 18994

Date 6-7-97



4) SURVEYS WERE RECORDED IN LIBER 1, PAGE 881, JUNE 5, 1973 AND IN LIBER 2, PAGES 561-563, JUNE 20, 1975 ALONG WITH A L.C.R.C. RECORDED IN LIBER 3, PAGE 113, FIELD DATED 4-10-1974, BY O. BOSS P.S. NO. 13574

4" I-BEAM FOUND, 1/2" RE-ROD SET

N83 DEG. W, 27.06', NAIL S/S 28" TREE
S65 DEG. W, 33.92', NAIL, N/S 40" MAPLE
S42 DEG. E, 28.0', NAIL, N/S 32" MAPLE

5) SURVEY BY M. FOUTY, P.S. NO. 18989, DATED MARCH 3, 1978, LIBER 3, PAGE 555 CALLED FOR A 1/2" BAR WITH WITNESSES THE SAME AS 4-A ABOVE.

RECORDED
INDEXED
SERIALIZED
FILED
MAY 1978
LIBER 9