

**SURVEY &
REMONUMENTATION**

JAN 18 2001

Paula Johnson
INGHAM COUNTY
REGISTER OF DEEDS
RON HELSEL

RECORDED

L-10 P-8

CRNR 9.00

2000-044602

2000-044602

Page: 1 of 1

10/18/2000 11:02A



SECTION

**LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
LOCKE TOWNSHIP**

For corners in

<u>INGHAM</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4N</u> R <u>2E</u>	<u>J-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, RON HELSEL, in a field survey on SEPT. 26, 2000 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL MONUMENT: POST SET BY J. WAMPLER, U.S. DEPUTY SURVEYOR, APRIL, 1826. SET AT AVG. DISTANCE 39.95 CHAINS; ASH 8", NORTH, 34 LINKS; ASH 10", N82W, 14 LINKS.

1) VOL. 2, PAGE 181, & VOL. 2, PAGE 182, NOV. 18 AND DEC. 2, 1879, CO. SURVEYOR, A.P. DRAKE. CALLED FOR A STONE; W. O. 4", N15-1/2W, 93-1/2 LINKS; W.O. 2-1/2", S70E, 55-1/2 LINKS. 40.25 CHAINS TO K-11, 39.89 CHAINS TO I-11 & 40.0 CHAINS TO J-12.

2) P. A. 74 CORNER, LIBER 3, PAGE 113, APRIL 10, 1974, O. BOSS, P.S. 13574. "IRON SET IN OLD HOLE OF OLD FENCE POST INTERSECTION." S80°W, 13.89 FT. NAIL S/S 8" TREE
S62°W, 12.17 FT. NAIL S/S 6" TREE
S17°E, 24.63 FT. NAIL W/S 6" TREE
3) P.A. 132 SURVEY, LIBER 1, PAGES 979-980, AUG. 16, 1973 BY O. BOSS GAVE THE SAME MONUMENT AND WITNESSES AS ABOVE.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND 1/2" REBAR IN HOLE OF A CIRCLE OF STONES IN REMAINS OF AN EAST-WEST FENCE LINE. NEXT TO A COIL OF FENCE APPARENTLY TORN OUT FROM THE LINE TO THE SOUTH. CORNER 300' WEST MORE OR LESS FROM A GRAVEL FARM LANE RUNNING NORTH FROM THE SECTION LINE. FOUND ONE REMAINING BEARING TREE (S17E, 24.63) WITH L. BRYAN NAIL AND TAG #25832 LYING ON THE GROUND. EXCAVATED DOWN 2± AND FOUND A 4" DIAMETER BROKEN FIELD TILE 6" WEST OF THE IRON BAR. ACCEPTED THE POSITION OF THE 1/2" BAR AS FAITHFUL PERPETUATION OF THE CORNER AND REPLACED WITH 3/4" BY 24" IRON PIN AND STANDARD INGHAM COUNTY DISK STAMPED P.A. 345, P.S. 18994. CORNER WAS IN VERY CLOSE ACCORD WITH DRAKES SURVEY, VOL. 2, PAGE 182.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

3/4" BY 24" FORM PIN AND STANDARD DISK IN EAST-WEST FENCE LINE.
SET NEW NAIL IN L. BRYAN TAG #25832 WEST/SIDE 12" BASSWOOD, N. AZ. 164°, 24.52 FEET
SET NAIL & TAG #18994 SW/SIDE 16" MAPLE, N. AZ. 134°, 44.42 FEET
SET NAIL & TAG #18994 SOUTH/SIDE 12" BASSWOOD, N. AZ. 88°, 12.70 FEET
SET NAIL & TAG #18994 SOUTH/SIDE 18" HICKORY, N. AZ. 274°, 29.32 FEET
MEAS. SOUTH, 2639.21 FEET TO J-12 (DRAKE 2640.00 FEET)
MEAS. EAST, 2651.04 FEET TO K-11 (DRAKE 2656.50 FEET)
MEAS. WEST, 2630.84 FEET TO I-11 (DRAKE 2632.74 FEET)

Register of Deeds Stamp & File Number

1	A	B	C	D	E	F	G	H	I	J	K	L
2		6		5		4		3		2		1
3												
4		7		8		9		10		11		12
5												
6		18		17		16		15		14		13
7												
8		19		20		21		22		23		24
9												
10		30		29		28		27		26		25
11										●		
12		31		32		33		34		35		36
13												



Signed by Ron Helsel
Surveyor's Michigan License No. 18994

Date Oct 7 00

P.A. 345 INGHAM COUNTY
PEER APPROVED 10/3/2000 M