

DEC 17 1998

SECTION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Liber 9 Page 393

For corners in

<u>INGHAM</u>	Located In:	Corner Code #
(County)	LOCKE TOWNSHIP	
1. Public Land Survey	T <u>4N</u> R <u>2E</u>	<u>L-13</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

FILED

980057070
11/06/1998 14:25:51
REGISTER OF DEEDS
Paula Johnson
INGHAM COUNTY, MI

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, RON HELSEL, in a field survey on OCTOBER 15, 19 98 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

1	A	B	C	D	E	F	G	H	I	J	K	L	M
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL MONUMENT: POST SET BY UNKNOWN U.S. DEPUTY SURVEYOR, FEB. 1824 SET AT 40 CHAINS; WHITE OAK 3", N51 1/2W 10 LINKS; WHITE OAK 3", N62 1/2E 6 LINKS.


- 1) VOL. 3, PAGE 219, MAY 5,6 &7, 1890, COUNTY SURVEYOR J. McCREARY CALLED FOR A HEWED SQUARE ELM STAKE; WHITE OAK 48", N51W 1 1/2 LINKS; ELM 16", N72 1/4E 47 LINKS
- 2) FOLDER SET #2, PAGE 46, UNKNOWN DATE OR COUNTY SURVEYOR DID NOT WITNESS THIS CORNER
- 3) AL-MAR RIVERSIDE ESTATES, L. HENDRYX NO. 3276, VOL 29, PAGE 34, 1966 REFERS TO THIS CORNER.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
TRAVERSED TO AREA WHICH IS IN THE MIDDLE OF A PLOWED FIELD. MEASURED 5296.00 FEET BETWEEN THE STANDARD CORNERS M-13 AND K-13. SET TEMPORARY POINT AT THE MIDPOINT OF THE SOUTH LINE OF SECTION 36. TRAVERSE COMPUTATIONS FROM THE PLAT OF AL-MAR RIVERSIDE ESTATES LOCATED A POINT 28 FEET MORE OR LESS NORTH AND EAST OF THE MIDPOINT. DID NOT FIND ANY FENCE LINES OR SUPPORTING EVIDENCE OF SURVEYOR HENDRYX'S PLAT TIES TO THE CORNER. REPLACED TEMPORARY POINT AND SET A 3/4" X 24" FORM PIN AND INGHAM COUNTY DISK 2.0 FEET DEEP INTO THE PLOWED FIELD AS THE POSITION FOR A LOST CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
3/4" X 24" FORM PIN AND DISK STAMPED P.A. 345, P.S. 18994, 2 FEET DEEP IN PLOWED FIELD
MEASURED N88°15'55"W, 2648.00 FEET TO K-13
MEASURED S88°15'55"E, 2648.00 FEET TO M-13
MEASURED S88°15'55"E, 10.56 FEET TO L-1 LEROY TWP. T3N, R2E
MEASURED N03°23'02"W, 1025.77 FEET TO A CONCRETE MONUMENT AT THE NORTHEAST CORNER OF LOT 10 OF THE PLAT OF AL-MAR RIVERSIDE ESTATES.
BEARINGS RELATIVE TO THE NORTHERLY LINE OF AL-MAR RIVERSIDE ESTATES AND THE CENTERLINE OF ALLEN ROAD RECORDED AS: N63°14'E.

Signed by Ron Helsel
Surveyor's Michigan License No. 18994

Date Oct. 30, 1998



P.A. 345 INGHAM COUNTY
PEER APPROVED: 10/20/98