



SEP 01 1999

(PART A CONTINUED)

## SECTION

5. Ingham County Road Commission grid map, revised Jan. 1, 1972, calls out the following: Mon box (MSHD 1969)  
NW cor. CB S40W 23.0'; Brick Wall N65E 61.3'; Brick Wall S45E 63.8'; 85' N of e Grand River Ave.
6. Act 132 Survey by James E. Stephens, P.S. 16053, recorded in Liber 1, Page 1250, dated May 16, 1974, refers to corner, but does not give corner material or witnesses. Refers to Liber 2, Page 148 LCRC
7. Act 74 Certificate recorded in Liber 2, Page 147, dated November 7, 1972, by Clyde K. Stephens RLS #3829 recorded corner as a 3/4" iron pipe in a monument box, witnessed by: N59°21'E 61.30 feet to the NW corner of a brick wall around a swimming pool.  
S54°53'E 63.80 feet to the SW corner of a brick wall around a swimming pool.  
S41°59'W 23.00 feet to the NW corner of a catch basin  
The section line north of the corner was assigned a bearing of N0°19'15"W
8. Act 74 Certificate recorded in Liber 6, Page 390, dated August 16, 1988 by Mark W. Witalec PS 30897 recorded corner as a 1/2" pipe in a monument box, witnessed by: SW, 23.00' to NW corner of a C.B. casting  
SW, 62.98' to near side of conc. light pole  
ENE, 40.00' to nail & tag #28414 in south side of a 12" Maple tree  
E, 18.33' to back of conc. curb  
(On the certificate, Mr. Witalec noted that this corner is consistant with MDOT 280 card. This surveyor could not find this card.)
9. Act 74 Certificate recorded in Liber 7, Page 114, by Maurice H. Mahieu, P.S. #28414 dated March 29, 1989 calls for corner to be a 3/4" iron pipe in a monument box, witnessed by: NW corner of a catch basin, S42°W 23.00 feet  
SW corner of a brick sign base at ground level S65°E 50.82 feet  
Nail and tag in 12" Maple, N80°E 40.00 feet  
PK nail in northerly pole of billboard support, N40°W 60.54 feet

