

**SURVEY & REMONUMENTATION**

**REMONUMENTATION**

FEB 18 1994

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

Ionia (County)

Located In:

Corner Code ##

- |                                    |                         |            |
|------------------------------------|-------------------------|------------|
| 1. Public Land Survey              | T <u>5N</u> R <u>5W</u> | <u>A-6</u> |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
|                                    | T _____ R _____         | _____      |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |
| 3. Miscellaneous Property in Sec.  | S _____ T _____ R _____ | _____      |
|                                    | S _____ T _____ R _____ | _____      |

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
 IONIA COUNTY  
 RECEIVED FOR RECORD  
 93 DEC 27 P 1:11  
 Duane M. Ankrom  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Marinus Mulder, in a field survey on October 15, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	8	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

This closing corner was not set by the G.L.O. Surveyors. Historical establishment and/or perpetuation: D.C. Crawford former Ionia County Surveyor performed a survey April 18, 1890 in Section 18, T5N-R5W which is found in Volume 2 page 120 of the County Surveyor's records. Crawford shows no witnesses to this corner. The Ionia County Road Commission shows witnesses to the corner which were taken when Keefer Highway was being reconstructed in 1962. They call for a 1" iron but the road plans do not state what was found. This corner was recorded by Professional Surveyor, Duane Ankrom #21265 in March of 1977 found in Liber 1 page 228. Ankrom found a boat spike 6" below road surface and set a 1/2" rod & cap above it. Professional Surveyor, Russell Roon #13593 re recorded Ankrom's corner November 1978 recorded in Liber 2 page 88.

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found Ankrom's rod & cap at the pavement surface. Dug beneath this and found a 1" boat spike, but found nothing below boat spike or next to it, to a depth of 30". Accepted this as the position for A-6 and set a 30" fiberglass monument in place of the 1" boat spike and 1/2" rod & cap.

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- Set a 30" fiberglass monument with a 4" diameter bronze cap stamped "Ionia County Survey Monument - Do Not Disturb" witnessed by:
- Nail & tag North side wood post N 57° W 30.65'
- Nail & tag Southeast side 5" Osage Orange S 37° W 62.05'
- Nail & tag Southwest side 6" Boxelder S 60° E 99.66'
- Nail & tag Northwest side 6" Boxelder N 25° E 31.04'
- East 1/4 corner Section 13, T5N-R6W North 14.83'

Signed by Marinus Mulder Date November 2, 1993

Surveyor's Michigan License No. 25863